



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 4, 2013

SUBJECT: FAU 2783 (Ridgeland Ave. & Marion St.)
Project TE-00D1(861)
Section 11-00253-00-LS (Oak Park)
Cook County
Contract No. 63722
Item 139
March 8, 2013 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Revised Index of Special Provisions.**
- 2. Added page 172 to the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

INDEX OF SPECIAL PROVISIONS

LOCATION OF PROJECT.....	1
DESCRIPTION OF PROJECT.....	1
STATUS OF UTILITIES TO BE ADJUSTED.....	2
TRAFFIC CONTROL PLAN.....	2
TRAFFIC CONTROL AND PROTECTION (SPECIAL).....	3
PROTECTION OF EXISTING FACILITIES.....	3
ORNAMENTAL METAL PANEL.....	4
ANCHOR BOLTS, EXPANSION BOLTS, AND RESIN ANCHORS.....	11
GATEWAY MONUMENT SIGN COMPLETE.....	13
SIGN TO BE RELOCATED.....	20
BRICK PAVER REMOVAL.....	27
RAILROAD AGREEMENT FOR SERVICES.....	28
GENERAL ELECTRICAL REQUIREMENTS.....	31
ELECTRIC UTILITY SERVICE CONNECTION.....	34
ELECTRIC SERVICE INSTALLATION.....	35
EXPOSED RACEWAYS.....	36
WIRE AND CABLE.....	39
LIGHTING UNIT COMPLETE.....	40
ILUMILINE 36 IP OPTIC 30 RGB.....	41
ILUMIPOD 7 IP OPTIC 18 VW 2:1.....	42
LIGHTING CONTROLLER, SPECIAL.....	42
BICYCLE RACKS.....	43
BICYCLE RACKS TO BE MOVED.....	46
BIKE SHELTER.....	46
CONCRETE PAD.....	48
PROTECTIVE SHIELD, SPECIAL.....	48
VEHICLE CONTROL BOLLARDS.....	48
ART PANEL.....	53
PIGEON NETTING.....	54
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION {TPG}.....	54

PLAN NOTES

172

Revised 3/4/13

To further clarify the design plans, the following notes are provided.

- On sheet 13, the material for the floral pattern shall be ¼" thick laser cut steel plate.
- On sheet 14, the thickness of the plates shall be ¼" laser cut steel.
- The polycarbonate thickness shall be per the manufacturer's recommendations.
- The raised letter dimensions are 1'-2 ¾" high times new roman style.
- For section A-A, the length of the plate is shown on sheet 11, the length of plate for section A-A. The protective shield, special is 78' long.
- The graphic on sheet 22 is for informational purposes only. Not all ornamental metal panels will have a curved arch ceiling. Refer to sheet 17 for curved arch ornamental metal panel locations as dimensioned and noted with a double asterisk (**). Ornamental metal panels will have 3 curved arches for the first 3 ornamental metal panels are the ends of the viaduct. Curved arch canopy construction consists of ¼" thick painted aluminum sheet secured to panel supports. Refer to sheet 20.
- Ornamental metal panels on sheet 17 are to be designed by the Contractor including the connection of the ¼" painted aluminum sheet to the 4" angle iron bent/rolled to shape. On sheet 20, the plans indicate the 4" angle iron final size to be determined by the Contractor.