SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE 90% FEDERAL 10% STATE ROADWAY 0004 RURAL	CONST. CODE 90% FEDERAL 10% STATE BRIDGE 0011 STRUCTURE NO. 038-0215 RURAL	CONST. CODE 90% FEDERAL 10% STATE BRIDGE 0011 STRUCTURE NO. 038-0216 RURAL
28000500	INLET AND PIPE PROTECTION	EACH	8	8		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1005		502	503
28200200	FILTER FABRIC	SQ YD	1005		502	503
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	8815	8815		
31102100	SUBBASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	1264	1264		
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	3416	3416		
• 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	183	183		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1.0	1.0		
• 40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	325	325		
40603520	POLYMERIZED HOT•MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	113	113		
• 40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	185	185		
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	4054	4054		
42000536	PORTLAND CEMENT CONCRETE PAVEMENT 11 3/4" (JOINTED)	SQ YD	1561	1561		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1701	1701		

PLAN — NOTE BOOK NO. — CORRECTED / PLOTTED / ALIGNMENT CHECKED / PLAN MARKED / CADD FILE NAME — BY — DATE

PROFILE — NOTE BOOK NO. — CORRECTED / PLOTTED / GRADES CHECKED / PROFILE MARKED / STRUCTURE NOTATIONS CHKD — BY — DATE

FILE NAME = c:\pw_work\pwidot\bhagarbsh\d-68829\D366944_sht_soq_02-mn.dgn

Wight

USER NAME = dumcanbd	DESIGNED BAH	REVISED	
	DRAWN BAH	REVISED	
PLOT SCALE = 1.00 ' / in.	CHECKED KAC	REVISED	
PLOT DATE = 12/10/2012	DATE 12/07/2012	REVISED	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERSTATE 57 OVER LANGAN CREEK
SUMMARY OF QUANTITIES

SCALE: | SHEET 2 OF 9 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	141 BR(SB) & 38-1 BR(NB)	IROQUOIS	138	4

CONTRACT NO. 66944

ILLINOIS FED. AID PROJECT