

**SUMMARY OF QUANTITIES**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE	CONST. CODE	CONST. CODE
				90% FEDERAL	90% FEDERAL	90% FEDERAL
				10% STATE	10% STATE	10% STATE
				ROADWAY	BRIDGE	BRIDGE
0004	0011	0011				
				RURAL	STRUCTURE NO. 038-0215	STRUCTURE NO. 038-0216
				RURAL	RURAL	RURAL
44000100	PAVEMENT REMOVAL	SQ YD	2544	2544		
44000177	HOT-MIX ASPHALT SURFACE REMOVAL, 7"	SQ YD	2320	2320		
44004000	PAVED DITCH REMOVAL	FOOT	230	230		
44004250	PAVED SHOULDER REMOVAL	SQ YD	3072	3072		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	38	38		
44201299	DOWEL BARS 1 1/2"	EACH	1856	1856		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1246	1246		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1447	1447		
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	294	294		
48203025	HOT-MIX ASPHALT SHOULDERS, 7"	SQ YD	2320	2320		
48203038	HOT-MIX ASPHALT SHOULDER 10 1/4"	SQ YD	1858	1858		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1
50104650	SLOPE WALL REMOVAL	SQ YD	1257		628	629

PLAN	DATE
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	

PROFILE	DATE
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	
BY	
REVISION	
DATE	

FILE NAME = 0358944.pha.sq.D3.dgn



USER NAME = khonricho	DESIGNED BAH	REVISED
	DRAWN BAH	REVISED
	CHECKED KAC	REVISED
	DATE 12/07/2012	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**INTERSTATE 57 OVER LANGAN CREEK  
SUMMARY OF QUANTITIES**

SCALE: SHEET 3 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	141 BRISB & 38-1 BRINB	ILLINOIS	138	5
CONTRACT NO. 66944			ILLINOIS FED. AID PROJECT	