SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE 90% FEDERAL 10% STATE ROADWAY 0004 RURAL	CONST. CODE 90% FEDERAL 10% STATE BRIDGE 0011 STRUCTURE NO. 038-0215 RURAL	CONST. CODE 90% FEDERAL 10% STATE BRIDGE 0011 STRUCTURE NO. 038-0216 RURAL
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	12	12		
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	447	447		
	60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2		
	60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	3	3		
Δ	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1187.5	1187.5		
Δ	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6		
Δ	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
	63200310	GUARDRAIL REMOVAL	FOOT	1822	1822		
	63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	1	1		
	63500105	DELINEATORS	EACH	12	12		
	63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	5063	5063		
	64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	8435	8435		
	64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	35	35		

14

Δ Specialty Items

PLAN: SURVEYED, PLOTTED, ALIGNMENT CHECKED, PT. OF WAY CHECKED, CADD FILE NAME, NOTE BOOK NO., BY, DATE

PROFILE: SURVEYED, PLOTTED, GRADES CHECKED, B.M. NOTED, STRUCTURE NOTATNS CHKD, NOTE BOOK NO., BY, DATE

FILE NAME = D366944_sht_sog_06.dgn

Wight

USER NAME = bhoerichs	DESIGNED BAH	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN BAH	REVISED	
PLOT SCALE = 1.00 ' / IN.	CHECKED KAC	REVISED	
PLOT DATE = 12/7/2012	DATE 12/07/2012	REVISED	

INTERSTATE 57 OVER LANGAN CREEK
SUMMARY OF QUANTITIES

SCALE: | SHEET 6 OF 9 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	141 BR(SB) & 38-1 BR(NB)	IROQUOIS	138	8

CONTRACT NO. 66944

ILLINOIS FED. AID PROJECT