

EARTHWORK SCHEDULE							
STAGE	LOCATION		EARTH EXCAVATION	EARTH EXCAVATION FOR EROSION CONTROL	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	BALANCE WASTE (+) OR SHORTAGE (-)
	FROM	TO	CU YD	CU YD	CU YD	CU YD	CU YD
STAGE 1	141+96.00	153+00.00	562		422	1993	-1571
	147+17.00			12*			
	153+00.00			4	3		3
STAGE 3	141+96.00	153+50.00	1703		1277	596	681
TOTAL			2265	16	1702	2589	-887

NOTES:
 1. ASSUME 25% SHRINKAGE
 • NOT SUITABLE FOR EMBANKMENT

TEMPORARY PAVEMENT MARKING SCHEDULE							
LOCATION		DESCRIPTION	SHORT TERM PAVEMENT MARKING	TEMP PAVEMENT MK - LINE 5"	TEMP PAVEMENT MK - LINE 24"	WORK ZONE PAVT MK REM	
SIDE	STA		FOOT	FOOT	FOOT	SQ FT	
RT	140+62.00 TO 152+50.00	- RUNAROUND	EDGE LINE	1221		510	
LT	141+98.00 TO 151+79.30	- RUNAROUND	EDGE LINE	982		409	
CL*	140+52.00 TO 153+73.00		SKIP DASH	340		142	
CL*	148+96.59 TO 153+73.00		SOLID NPZ	477		199	
LT*	141+98.00 TO 153+50.00		EDGE LINE	1152		480	
RT*	142+00.00 TO 153+50.00		EDGE LINE	1150		480	
CL	140+52.00 TO 153+73.00		SKIP DASH	272		57	
LT	141+98.00 TO 153+50.00		EDGE LINE	96		20	
RT	142+00.00 TO 153+50.00		EDGE LINE	96		20	
RT	140+52.00		STOP BAR		11	22	
LT	153+73.00		STOP BAR		11	22	
TOTAL				464	5322	22	2361

PAVEMENT MARKING SCHEDULE						
LOCATION		DESCRIPTION	PAINT PAVEMENT MARKING - LINE 5"	PAVEMENT MARKING REMOVAL	RAISED REFL PVMT MKR	RAISED REFL PVMT MKR REMOVAL
SIDE	STA		FOOT	SQ FT	EACH	EACH
CL	140+52.00 TO 142+62.00	SKIP DASH		25		
CL	140+00.00 TO 154+00.00	SKIP DASH	350		19	19
LT	140+00.00 TO 154+00.00	EDGE LINE	1400			
RT	140+00.00 TO 154+00.00	EDGE LINE	1400			
LT	141+98.00 TO 144+23.22	EDGE LINE		95		
LT	149+53.75 TO 151+79.30	EDGE LINE		95		
CL	148+96.59 TO 154+00.00	SOLID NPZ	504			
CL	151+13.00 TO 153.73.00	SKIP DASH		30		
CL	151+13.00 TO 153.73.00	SOLID NPZ		109		
TOTAL			3654	354	19	19

SEEDING SCHEDULE							
LOCATION		SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
SIDE	STA	ACRE	POUND	POUND	POUND	TON	ACRE
LT	141+96.00 TO 146+90.00	0.4	36	36	36	0.8	0.4
LT	147+10.00 TO 153+50.00	0.75	68	68	68	1.5	0.75
RT	142+00.00 TO 146+74.00	0.15	14	14	14	0.3	0.15
RT	147+01.00 TO 153+50.00	0.2	18	18	18	0.4	0.2
TOTAL		1.5	136	136	136	3	1.5

PAVEMENT SCHEDULE													
LOCATION		HMA SURFACE CSE, MIX "C", N50	LEVELING BINDER (MM), N50	HMA BINDER CSE, IL-19.0, N50	HMA SURFACING BASE CSE WIDENING, 6.5"	HMA SURFACING BASE CSE WIDENING, 8"	HMA BASE CSE, 8"	HMA BASE CSE, 12"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HOT-MIX SURFACING	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
SIDE	STA	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD
	142+00.00 TO 142+05.00												14
	140+00.00 TO 154+00.00	366							6	9		85	
	140+00.00 TO 146+52.49				218	218							
	146+52.49 TO 146+95.00							108					
	140+00.00 TO 154+00.00							78					
	147+15.16 TO 147+45.66				219	219							
LT	142+29.50 TO 151+45.50						1458						
	153+45.00 TO 153+50.00												14
RT	152+62.00 - PE									5			
	140+45.00 TO 153+55.00		275										
	146+00.00 TO 148+00.00			156									
TOTAL		366	275	156	437	437	1458	186	6	9	5	85	28

ESTIMATED QUANTITIES SCHEDULE					
LOCATION		AGGREGATE FOR TEMPORARY ACCESS	PAVEMENT PATCHING, TYPE II, 12"	PAVEMENT PATCHING, TYPE III, 12"	PAVEMENT PATCHING, TYPE IV, 12"
SIDE	STA	TON	SQ YD	SQ YD	SQ YD
LT	146+40.00	59			
	140+00.00 TO 154+00.00		99	80	40
TOTAL		59	99	80	40

FILE NAME = c:\new-work\pmdot\sparksgw\0832885\0672B62-sht-schedule.dgn
 MODEL = \$MODEL\$
 PLOT DRIVER = \$PLTDVRS\$



USER NAME = sparksgw	DESIGNED - MCV	REVISED -
FILE NAME = 0672B62-sht-schedule.dgn	DRAWN - CMM	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED - MTM	REVISED -
PLOT DATE = Dec-18-2012 10:19:29AM	DATE - 12/12	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-4	HANCOCK	57	11
CONTRACT NO. 72B62				
ILLINOIS FED. AID PROJECT				