

X0326898 CENTERLINE - RUMBLE STRIP - 16"				
"FROM" STATION	"TO" STATION	LENGTH FT	GAP FT	
MENARD COUNTY				
84+70	93+80	910		
93+80	120+53		2673	HARGRAVE ST AND CE
120+53	138+81.73	1829		
138+81.73 BK	139+88.70 AH	STATION EQUATION		
139+88.70	140+00	12		
140+00	151+50		1150	ATHENS
151+50	165+20	1370		
165+20	166+55		135	HACKMAN RD/TILSON SCHOOL AVE
166+55	219+35	5280		
219+35	221+35		200	JOHNSON RD/SHANGHI LN
221+35	270+19.96	4885		
270+19.96 BK	270+60.46 AH	STATION EQUATION		
270+60.46	275+85	525		
275+85	276+85		100	INDIAN POINT RD/QUARRY RD
276+85	318+75	4190		
318+75	337+25		1850	IL 123
337+25	341+75	450		
341+75	353+25		1150	CE
353+25	384+00	3075		
384+00	385+50		150	JELLYSTONE RD
385+50	438+48	5298		
438+48	439+48		100	HAGNEY RD/SWEETWATER RD
439+48	455+62.05	1615		
455+62.05 BK	455+82.01 AH	STATION EQUATION		
455+82.01	477+15	2133		
477+15	478+15		100	UNNAMED ROAD
478+15	495+50	1735		
495+50	497+00		150	EVERETT AVE/AMVETS ST
497+00	524+55	2755		
524+55	525+55		100	HOPPLER RD
525+55	556+75	3120		
556+75	557+75		100	CE
557+75	566+00	825		
566+00	581+70		1570	GREENVIEW
581+70	626+30	4460		
626+30	627+30		100	CE
627+30	656+30	2900		
656+30	657+30		100	MIDDLETOWN AVE
657+30	732+50.94	7521		
732+50.94 BK	732+49.96 AH	STATION EQUATION		
732+49.96	750+12	1763		
750+12	757+00		688	S. N. 065-0001 ( SALT CREEK )
MENARD COUNTY TOTAL		56,651	10,416	

X0326898 CENTERLINE - RUMBLE STRIP - 16" (CONTINUED)				
"FROM" STATION	"TO" STATION	LENGTH FT	GAP FT	
MASON COUNTY				
757+00	764+63.79		764	S. N. 065-0001 ( SALT CREEK )
764+64	784+49.53	1986		
784+49.53 BK	33+22.93 AH	STATION EQUATION		
33+22.93	49+75	1653		
49+75	50+75		100	MAXFIELD ROAD ( E CO RD 580 N )
50+75	115+30	6455		
115+30	116+30		100	E CO RD 700 N
116+30	157+68.00	4138		
157+68	158+68.00		100	N CO RD 3350
158+68	169+56.79	1089		
169+56.79 BK	170+11.30 AH	STATION EQUATION		
170+11.30	176+58	647		
176+58	177+60		102	E CO RD 800 N
177+60	203+14	2554		
203+14	204+14		100	OLD ROUTE 29
204+14	244+00	3986		
244+00	245+00		100	E CO RD 930 N
245+00	254+50	950		
254+50	255+50		100	E CO RD 3380 E
255+50	263+11.04	762		
263+11.04 BK	263+14.43 AH	STATION EQUATION		
263+14.42	263+86	72		
263+86	264+86		100	E CO RD 940 N
264+86	269+00	414		
263+86	270+65.38		679	CE
MASON COUNTY TOTAL		24,706	2,245	

TOTAL = 81,357 FEET

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
c:\pw\work\p1dot\sparksgw\0328123\067293-sht-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = Dec-19-2012 02:43:11PM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	D6 RUMBLE STRIP 2013	*	39	5
CONTRACT NO. 72F93			ILLINOIS FED. AID PROJECT	