- 1. VERIFICATION OF DIMENSIONS AND GRADES, BOTH EXISTING AND PROPOSED, SHALL BE THE CONTRACTOR'S RESPONSIBILITY PRIOR TO COMMENCEMENT OF WORK. THE CONTRACTOR SHALL NOTIFY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST, 618-346-3198 OF ANY DISCREPANCIES.
- 2. ALL SURFACE DRAINAGE SHALL BE DIRECTED AWAY FROM BUILDINGS. SURFACE DRAINAGE SHALL BE DIRECTED TO EXISTING DRAINAGE STRUCTURES DESIGNATED FOR THE COLLECTION OF SURFACE RUN-OFF.
- 3. CONTRACTOR SHALL REPAIR IN KIND ANY AREAS DAMAGED AS A RESULT OF LANDSCAPE OPERATIONS AT NO ADDITIONAL COST TO THE CONTRACT.
- 4. ALL SEEDING, CLASS 2A AREAS SHALL HAVE FERTILIZER APPLIED AS FOLLOWS:
 NITROGEN FERTILIZER NUTRIENT 90 LBS/ACRE
 PHOSPHORUS FERTILIZER NUTRIENT 90 LBS/ACRE
 POTASSIUM FERTILIZER NUTRIENT 90 LBS/ACRE
- 5. ALL SEEDING, CLASS 4A AND SEEDING, CLASS 4B AREAS SHALL NOT REQUIRE FERTILIZER NUTRIENTS.
- 6. EROSION CONTROL BLANKET SHALL BE APPLIED TO ALL SEEDED AREAS, EXCEPT AREAS WITH SEEDING, CLASS 4B AS SHOWN IN THE PLANS. THE SEEDING, CLASS 4B AREAS SHALL HAVE MULCH, METHOD 2 NOT EROSION CONTROL BLANKET.
- 7. SUPPLEMENTAL WATERING SHALL BE APPLIED AT THE DIRECTION OF THE ENGINEER AT A RATE OF 3 GAL/SO YD, OR AT THE RATE DIRECTED BY THE ENGINEER.
- 8. THE SEEDING SHOWN IN THESE PLANS SHALL SUPERCEDE THE PERMANENT CONFLICTING SEEDING SHOWN IN PREVIOUS MRB CONTRACTS.
- 9. THE CONTRACTOR SHALL COORDINATE THE LANDSCAPING PLANTING SCHEDULE WITH CONTRACTS 76C43, 76C50, 76C76, 76D05 AND 76E06 TO ENSURE THAT THE EMBANKMENT GRADES ARE FINALIZED AT THE LIMITS OF ALL CONTRACTS AND THE PROPOSED LANDSCAPING IMPROVEMENTS CAN BE CONSTRUCTED WITHOUT CONFLICT.
- 10. SELECTIVE MOWING STAKES SHALL NOT BE REQUIRED FOR THIS CONTRACT.
- 11. CONTRACTOR SHALL CONTACT DAVID WALKER IDOT ELECTRICAL SERVICES SUPERVISOR AT 618.346.3274 PRIOR TO CONSTRUCTION TO SCHEDULE A WALK THROUGH OF THE SITE TO IDENTIFY ALL DEEP WELLS AND I.T.S. EQUIPMENT PRIOR TO START OF WORK.
- 12. ALL TREES SHALL BE SPACED AT A MINIMUM 40' C-C AS SHOWN IN THE PLANS.
- 13. ABBREVIATION IP&P = INLET AND PIPE PROTECTION
- 14. IF THE PROPOSED PLANTINGS ARE TO BE LOCATED ON SLOPES 1V:4H OR STEEPER, OR ARE LOCATED IN UNDESIRABLE LOCATIONS, THE PLANTINGS SHALL BE RELOCATED. THE REVISED PLANTING LOCATIONS SHALL BE COORDINATED AND APPROVED BY THE ENGINEER. ANY CONTRACTOR EXPENSE RELATED TO THESE RELOCATIONS SHALL BE CONSIDERED INCIDENTAL TO PLANTING WOODY PLANTS, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

	ŏ.
	SAD
	3
	CIVIL
	100
	9-89
	\2086
	ANS_Ø7\22Ø2\2Ø868-ØØI\CIVIL\CAD\
	6
	\\FS-0044\AM\VAULT,D-TRANS_07\2202\20868-001\CIVIL\CAD\9
	ġ
	Ξ
	Ϋ́
	ξ
	4
	90
	Ŗ
	1
	9
	BONDHUJO
	Š
8	ш
Ξ	
묎	3:46
D8CONN-17-BORDER1.D0	12-17-2012, 14:08:46
-17	2
Š	2012
<u> </u>	17-
?	72

FILE NAME = USER

#FILEL#

TENG & ASSOCIATES, INC.
PLOT
ENGINEERS/ARCHITECTS/PLANNERS
PLOT

USER NAME = \$USER\$	DESIGNED	-	JM	REVISED -
	DRAWN	-	JB	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED	-	ACL	REVISED -
PLOT DATE = \$DATE\$	DATE	-	12/21/12	REVISED -