	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	0005 ROADWAY 90% HSIP(FED) 10% STATE COOK COUNTY	0005 ROADWAY 100% STATE COOK COUNTY	0021 SIGNALS 90% HSIP(FED) 10% STATE IL 43 AT CERMAK COOK COUNTY	0021 SIGNALS 50% NORTH RIVERSIDE 50% BERWYN IL 43 AT 23RD ST COOK COUNTY	0021 EVP 100% LOCAL NORTH RIVERSIDE COOK COUNTY	0021 INTERCONNECT 90% HSIP(FED) 10% STATE COOK COUNTY	0005 SIGNALS 90% HSIP(FED) 10% STATE OTHER ADA IMPROVEMENTS COOK COUNTY	0021 LIGHTING 100% TOLL CREDIT(FED) BERWYN COOK COUNTY				
	CODE NO	ITEM	UNIT													
*	81603051	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8	FOOT	1014								1014				
		GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE														
*	81603112	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8	FOOT	412								412				
		GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE														
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V	FOOT	1270								1270				
		(XLP-TYPE USE) 1/C NO. 10														
*	81800240	AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE	FOOT	780								780	1			
*	82110007	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION G	EACH	4								4				
*	82110008	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION H	EACH	8								8	1			
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	63								63				
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	6								6				
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	6								6				
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL	EACH	3						2	1					
		INSTALLATION														
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2			1	1								
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3827						3827						

* SPECIALTY ITEMS

1 REVISED SHEET 2/23/2024

USER NAME = Alan.Parayno	DESIGNED - RR	REVISED -	
	DRAWN - RR	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - LP	REVISED -	
PLOT DATE = 12/15/2023	DATE - 4/22/2022	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 43 (HARLEM AVE) AT CERMAK RD (22ND ST)

SCALE: - | SHEET 7 OF 14 SHEETS | STA. - TO STA. -

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2019-077-TS&SW	COOK	134	10

CONTRACT NO. 62J47

ILLINOIS FED. AID PROJECT

REV-SEP

MODEL: Default
FILE NAME: pw:\\ildot-pw.bentley.com:PWIDOT\Documents\IDOT Offices\District 1\Projects\P135713\CADData\Design\P135713-sht-SQQ.dgn