03-08-2024 LETTING ITEM 116

0

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

FOR INDEX OF SHEETS, SEE SHEET NO. 2

PROPOSED HIGHWAY PLANS

FAI ROUTE 57: I-57
I-90/94 (DAN RYAN EXPWY) TO WILL/KANKAKEE COUNTY LINE
SECTION FAI 57 23 57 LITTER
EXPRESSWAY CLEANING (DEBRIS/LITTER REMOVAL)
COOK & WILL COUNTIES

C-91-188-23

0 100' 200' 300' — 1"= 100' 0 10' 20' 30' — 1"= 10' 0 50' 100' — 1"= 50' 0 50' 100' — 1"= 40' 0 50' 100' — 1"= 30'

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

OR 811

PROJECT ENGINEER: RODRIGO LEDEZMA PROJECT MANAGER: J. ALAIN MIDY

(847) 705-4580 (847) 221-3056

CONTRACT NO. 62V02

LOCATION MAPS - SEE SHEET INDEX

*COOK & WI

D-91-134-23





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

INDEX OF SHEETS

- TITLE SHEET
- 2. INDEX OF SHEETS APPLICABLE STATE STANDARDS
- 3. SUMMARY OF QUANTITIES SCHEDULE OF CLEANING STARTING DATES
- 4. EXPRESSWAY CLEANING: I-57 (I-94 TO WILL/KANKAKEE COUNTY LINE)
- 5. TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)

STATE STANDARDS

701106-02 OFF-ROAD OPERATION MULTILANE, MORE THAN 15' AWAY

701426-09 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS


45 MPH

701901-09 TRAFFIC CONTROL DEVICES


USERNAME = rodrigo.ledezma DESIGNED -REVISED -REVISED -DRAWN -PLOT SCALE = 0.16666633 ' / in. CHECKED -REVISED -PLOT DATE = 12/11/2023 REVISED -DATE

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


TOTAL SHEET NO. 5 2 INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES FA.I. 57 COUNTY SECTION FAI 57 23 57 LITTER CONTRACT NO. 62V02 SCALE: NONE SHEET 000 OF 4 SHEETS STA. TO STA.




TYPICAL EXPRESSWAY CROSS-SECTION NO. 1




TYPICAL EXPRESSWAY CROSS-SECTION NO. 2



TYPICAL EXPRESSWAY CROSS-SECTION NO. 3



TYPICAL EXPRESSWAY CROSS-SECTION NO. 4



TYPICAL EXPRESSWAY CROSS-SECTION NO. 5

NOTES:

- 1. SCHEDULE MAY VARY AS DIRECTED BY THE ENGINEER.
- 3. NO WORK WILL BE ALLOWED DURING ANY LEGAL HOLIDAY PERIOD.
- 4. ALL SCHEDULES OF ANTICIPATED STARTING DATES SHOWN ARE TENTATIVE AS DETERMINED BY THE DEPARTMENT'S OPERATIONAL NEEDS.
- 5. NO DAILY CONTRACTOR WORK REQUESTS/ SCHEDULING SHALL BE AUTORIZED OR APPROVED TO START WHEN IT IS DETERMINED BY THE ENGINEER THAT WEATHER CONDITIONS WILL BE UNFAVORABLE. APPROVAL OF ALL DAILY CONTRACTOR WORK SCHEDULE REQUEST SHALL BE SOLELY DETERMINED BY THE ENGINEER AND OR PROJECT SUPERVISOR.
- 6. ALL SHOULDER CLOSURES SHALL BE IMMEDIATELY REMOVED DURING
 ALL ADVERSE WEATHER CONDITIONS <u>WITHOUT EXCEPTION</u>. INCLUDING BUT NOT
 LIMITED TO RAIN, WET ROAD SURFACE (SPRAY FROM TIRES), MIST, DRIZZLE,
 SLEET, SNOW, FOG AND ANY OTHER CIRCUMSTANCE DETERMINIED UNSAFE BY THE ENGINEER.
 THE CONTRACTOR SHALL IMPLEMENT THIS CONTRACT REQUIREMENT IMMEDIATELY WITHOUT
 WAITING FOR DEPARTMENT INSTRUCTIONS.
- 8. NO WORK WILL BE ALLOWED ON THE FOLLOWING DATES UNLESS IT IS CONSIDERED AN EMERGENCY, IMMEDIATE HAZARD OR ANY WORK AS DESIGNATED BY THE DEPARTMENT THAT REQUIRES FIRST PRIORITY CORRECTIVE ACTION:

EASTER HOLIDAY
MEMORIAL DAY HOLIDAY
INDEPENDENCE DAY HOLIDAY
LABOR DAY HOLIDAY
THANKSGIVING HOLIDAY
CHRISTMAS EVE / NEW YEARS HOLIDAY

SUMMARY OF QUANTITIES				соок	WILL
COMMUNITY OF ACCUMENTS		URBAN	100 % STATE 0044	100 % STATE 0044	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	EXPRESSWAY	EXPRESSWAY
X0326643	LITTER PICKING	MILE	375.6	237	138.6

USER NAME = rodrigo.ledezma	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 0.16666633 ' / in.	CHECKED -	REVISED -
PLOT DATE = 11/14/2023	DATE -	REVISED -

	SUMMARY OF QUANTITIES					
	SCHED	ULE OF	STAR	RTING	DATES	
SCALE:	SHEET	OF 1	SHEETS	STA.	ТО	

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

	NO.			
57 FAI 57 23 57 LITTER * 5	1			
CONTRACT NO. 62V0	02			
ILLINOIS FED. AID PROJECT				

