

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2846	55-1414R-RS	COOK	25	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000- STATE 100%	Y025 (PARKING) CITY OF BLUE ISLAND 50% 50% STATE	Y025 (PARKING) CITY OF BLUE ISLAND 100%		
20101000	TEMPORARY FENCE	FOOT	300	300				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	7	1			
40600300	AGGREGATE (PRIME COAT)	TON	37	35	2			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	5	1			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	286	286				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	91	91				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1485	1435	50			
42001300	PROTECTIVE COAT	SQ YD	135	120		15		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	17096	16521	575			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	550	500		50		
44002205	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 1/4"	SQ YD	1100	1100				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	585	585				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	115	115				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	400	400				
55039700	STORM SEWERS TO BE CLEANED	FOOT	700	700				
56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4				
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	12	12				
60255410	CATCH BASINS TO BE CLEANED	EACH	20	20				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	45	45				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000- STATE 100%	Y025 (PARKING) CITY OF BLUE ISLAND 50% 50% STATE	Y025 (PARKING) CITY OF BLUE ISLAND 100%		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1036	1036				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9065	9065				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1295	1295				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	150	150				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	176	176				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4171	4171				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9065	9065				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1295	1295				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150	150				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	176	176				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1				
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	425	425				
* 87900200	DRILL EXISTING HANDHOLE	EACH	4	4				
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	3	3				
* 88600100	DETECTOR LOOP, TYPE I	FOOT	225	225				
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	160	160				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	751	725	26			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5				
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	8	8				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES