

C62728

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	3091-RS-4	COOK	27	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE FIRST AVE.	URBAN 1000 100% STATE MADISON STREET			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	12.5	12.5				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34.75	30	4.75			
40600300	AGGREGATE (PRIME COAT)	TON	173	150	23			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	4	1.0			
40600895	CONSTRUCTING TEST STRIP	EACH	3	2	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	549	501	48			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	596	441	155			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1.5	1.5				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	590		590			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3750	3750				
42001300	PROTECTIVE COAT	SQ YD	525	525				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	74	74				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1820	1820				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	6900		6900			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37208	37208				
44000600	SIDEWALK REMOVAL	SQ FT	1820	1820				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1170	1130	40			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	685		685			
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1250	1250				
44004250	PAVED SHOULDER REMOVAL	SQ YD	13	13				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	450	410	40			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	344	242	102			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	730	370	360			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	44	44				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE FIRST AVE.	URBAN 1000 100% STATE MADISON STREET			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16	14	2			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	139	130	9			
60401030	FRAMES, TYPE 23	EACH	12	12				
60404950	FRAMES AND GRATES, TYPE 24	EACH	20	20				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	18	18				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	79	66	13			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2			
67100100	MOBILIZATION	L SUM	1	.5	.5			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	6	2			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2560	2370	190			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1202	1202				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35618	33268	2350			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6176	6176				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2802	2802				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1246	1246				
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	601	601				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	21746	21746				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	601	601				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35618	33268	2350			

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 12/22/2006

12/22/2006 10:45:43 AM