

|                     |          |                  |              |           |
|---------------------|----------|------------------|--------------|-----------|
| F.A. RTE.           | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
| 662                 |          | MACOUPIN         | 66           | 3         |
| STA.                |          | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |              |           |

(V,T) B-2

| SUMMARY OF QUANTITIES |  | UNITS | TOTAL QUANTITY        | CONSTR. CODE                            | CONSTR. CODE                                |      | CONSTR. CODE                                  |
|-----------------------|--|-------|-----------------------|---|---|------|---|
| PAY CODE NUMBER       | PAY ITEM DESCRIPTION                         |       | 80% FED.<br>20% STATE | RURAL ROADWAY 1000<br>80% FED 20% STATE | IL 4 BRIDGE<br>X081-2A<br>80% FED 20% STATE |      | IMPACT ATTEN.<br>SFTY-3N<br>80% FED 20% STATE |
| 20100110              | TREE REMOVAL (6 TO 15 UNITS DIAMETER)        | UNIT  | 138                   | 138                                     | -   | -    |   |
| 20100210              | TREE REMOVAL (OVER 15 UNITS DIAMETER)        | UNIT  | 134                   | 134                                     | -   | -    |   |
| <b>20200100</b>       | <b>EARTH EXCAVATION</b>                      |       |                       |   |   |      |   |
| 20700400              | POROUS GRANULAR EMBANKMENT, SPECIAL          | CU YD | 1526                  | 1526                                    |   | 269  |   |
| 25000200              | SEEDING, CLASS 2                             | ACRE  | 0.7                   | 0.7                                     | -   | -    |   |
| 25000400              | NITROGEN FERTILIZER NUTRIENT                 | POUND | 67                    | 67                                      | -   | -    |   |
| 25000500              | PHOSPHORUS FERTILIZER NUTRIENT               | POUND | 67                    | 67                                      | -   | -    |   |
| 25000600              | POTASSIUM FERTILIZER NUTRIENT                | POUND | 67                    | 67                                      | -   | -    |   |
| 25000700              | AGRICULTURAL GROUND LIMESTONE                | TON   | 1.5                   | 1.5                                     | -   | -    |   |
| 25100115              | MULCH, METHOD 2                              | ACRE  | 0.7                   | 0.7                                     | -   | -    |   |
| <b>25100635</b>       | <b>HEAVY DUTY EROSION CONTRL BLANKET</b>     |       |                       |   |   |      |   |
| 28000250              | TEMPORARY EROSION CONTROL SEEDING            | SO YD | 1600                  | 1600                                    | -   | -    |   |
| 28000400              | PERIMETER EROSION BARRIER                    | FOOT  | 500                   | 500                                     | -   | -    |   |
| 28001000              | AGGREGATE (EROSION CONTROL)                  | TON   | 10                    | 10                                      | -   | -    |   |
| 28100109              | STONE RIPRAP, CLASS A5                       | SO YD | 1,465                 |   |   | 1465 |   |
| 28200200              | FILTER FABRIC                                | SO YD | 1525                  |   |   | 1525 |   |
| <b>28400100</b>       | <b>GABIONS</b>                               |       |                       |   |   |      |   |
|                       |  | CU YD | 30.7                  |   |   | 30.7 |   |
| 40200800              | AGGREGATE SURFACE COURSE, TYPE B             | TON   | 5                     | 5                                       | -   | -    |   |
| 40600200              | BITUMINOUS MATERIALS (PRIME COAT)            | TON   | 1.2                   | 1.2                                     | -   | -    |   |
| 40600300              | AGGREGATE (PRIME COAT)                       | TON   | 6                     | 6                                       | -   | -    |   |
| 40600982              | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 276                   | 276                                     | -   | -    |   |

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

Rev.

PLOT DATE = 12/15/2006  
FILE NAME = c:\pwworkspace\10552866\vt\sheet\sumqty.dgn  
PLOT SCALE = 1/8"=1'-0" / IN.  
USER NAME = hmagnum1