

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	66	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

• (V,T) B-2

TREE REMOVAL		
LOCATION	TREE REMOVAL 6" TO 15"	TREE REMOVAL > 15"
	UNIT	UNIT
RT STA 446+52.80		20
RT STA 446+54.54		25
RT STA 446+52.29	14	
RT STA 446+75.06		26
RT STA 446+92.48	11	
LT STA 446+31.80	6	
LT STA 446+32.10	6	
LT STA 446+32.30	6	
LT STA 446+33.38	6	
LT STA 446+90.63	10	
LT STA 447+07.14	7	
LT STA 447+06.51	6	
LT STA 447+06.95	12	
LT STA 447+10.05		23
LT STA 447+14.14	13	
LT STA 447+15.17	6	
LT STA 447+16.09	8	
LT STA 447+32.91	8	
LT STA 447+40.20 (STUMP)		20
LT STA 447+39.78	9	
LT STA 447+42.39	10	
LT STA 447+40.99		20
TOTAL =	138	134

BITUMINOUS SHOULDERS					
LOCATION	LENGTH	BIT PAY WIDTH	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SHLDRS. (VAR. DEPTH)
	FOOT	FOOT	TON	TON	TON
LT STA 442+85.00 TO LT STA 446+20.10	335.10	6.0	0.07	0.37	26.1
LT STA 446+20.10 TO LT STA 448+00.10 - BRIDGE OMISSION					
LT STA 448+00.10 TO LT STA 450+71.08	270.98	6.0	0.06	0.30	21.1
LT STA 450+71.08 TO LT STA 450+95.07	23.99	6.0 TO 1.0	0.003	0.02	1.1
RT STA 442+67.00 TO RT STA 446+07.50	340.50	6.0	0.07	0.38	26.5
RT STA 446+07.50 TO RT STA 447+87.50 - BRIDGE OMISSION					
RT STA 447+87.50 TO RT STA 450+60.00	272.50	6.0	0.06	0.30	21.2
RT STA 450+60.00 TO RT STA 450+76.00	16.00	6.0 TO 1.0	0.002	0.01	0.7
TOTAL =			0	1.38	96.68

NOTE: SHOULDERS SHALL NOT CONTINUE THROUGH SIDE ROADS.

RESURFACING & BRIDGE APPROACH PAVEMENT							
LOCATION	LENGTH	WIDTH	PR BIT SURF CSE AREA	HOT-MIX ASPH SURF. REM. BUTT JOINT	TEMPORARY RAMPS	BITUMINOUS MATERIALS (PRIME COAT)	BRIDGE APPR PVT
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	TON	SQ YD
STA 441+00.00 TO STA 441+50.00 (RAMP)	50.00	24.00	133.3	80.00	13.33	0.05	0.00
STA 441+50.00 TO STA 442+67.00	117.00	24.00	312.0	0.00	0.00	0.12	0.00
STA 442+67.00 TO STA 442+85.00	18.00	23.00	46.0	0.00	0.00	0.02	0.00
STA 442+85.00 TO STA 446+13.80	328.80	22.00	803.7	0.00	0.00	0.31	
STA 442+13.80 TO STA 446+19.80							
STA 446+19.80 TO STA 447+49.80 - BR APPR. PVT.							108.33
STA 447+49.80 TO STA 447+57.80 - BRIDGE							
STA 447+57.80 TO STA 447+87.80 - BR APPR. PVT.							108.33
STA 447+87.80 TO STA 447+93.80							
STA 447+93.80 TO STA 450+44.72	250.92	22.00	613.4	0.00	0.00	0.23	
STA 450+44.72 TO STA 450+74.00	29.28	23.00	74.8	0.00	0.00	0.03	0.00
STA 450+74.00 TO STA 451+50.00	76.00	24.00	202.7	0.00	0.00	0.08	0.00
STA 451+50.00 TO STA 452+00.00 (RAMP)	50.00	24.00	133.3	80.00	13.33	0.05	0.00
TOTAL =				160	26.7	0.88	216.67

PLOT DATE = 1/30/2007
 FILE NAME = c:\projects\652685\shscheduladgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY
 DATE HORIZ. CHECKED BY