

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	66	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

AGGREGATE SHOULDERS

LOCATION	LENGTH	AGG WIDTH	AGGREGATE SHOULDERS
	FOOT	FOOT	TON
LT STA 441+00.00 TO LT STA 441+86.00	86.00	3.00	4.08
LT STA 442+85.00 TO LT STA 444+88.80	203.80	3.00	9.67
LT STA 444+88.80 TO LT STA 446+26.10	137.30	3.25	7.06
LT STA 446+26.10 TO LT STA 447+94.10 - BRIDGE OMISSION			
LT STA 447+94.10 TO LT STA 450+71.08	276.98	3.25	14.24
LT STA 450+20.40 TO LT STA 452+00.00	179.60	3.00	8.52
RT STA 441+00.00 TO RT STA 441+28.00	28.00	3.00	1.33
RT STA 442+67.00 TO RT STA 443+87.20	120.20	3.00	5.70
RT STA 443+87.20 TO RT STA 446+13.50	226.30	3.25	11.63
RT STA 446+13.50 TO RT STA 447+81.50 - BRIDGE OMISSION			
RT STA 447+81.50 TO RT STA 449+18.90	137.40	3.25	7.06
RT STA 449+18.90 TO RT STA 450+00.00	81.10	3.00	3.85
RT STA 450+76.00 TO RT STA 452+00.00	124.00	3.00	5.88
TOTAL =			73.15

ESTIMATED QUANTITIES

ITEMS	UNIT	TOTAL
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HANDLING TEMPORARY EROSION CONTROL (SEE SPECIAL PROVISIONS)		
AGGREGATE (EROSION CONTROL)	TON	10
TEMPORARY EROSION CONTROL SEEDING	LBS	200
PERIMETER EROSION CONTROL BARRIER	FOOT	500

SEEDING SCHEDULE

LOCATION	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHER. FERTILIZER NUTIRENT	POTASSIUM FERTILIZER NUTRIENT	AGRIC. GROUND LIMESTONE	MULCH METHOD 2	HEAVY DUTY EROSION CONTL BLANKET
	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD
NORTHWEST QUADRANT	0.35	31.5	31.5	31.5	0.7	0.35	1600
NORTHEAST QUADRANT	0.23	20.7	20.7	20.7	0.5	0.23	-
SOUTHWEST QUADRANT	0.02	1.8	1.8	1.8	0.04	0.02	-
SOUTHEAST QUADRANT	0.14	12.6	12.6	12.6	0.28	0.14	-
TOTAL	0.74	67	67	67	1.5	0.74	1,600.00

GUARDRAIL SCHEDULE

LOCATION	TBT T-1 SPL (TANGENT)	TERMINAL MARKER DIR. APPL.	TBT T-6	SPBGR T-A	GUARDRAIL MARKERS T-A	GUARDRAIL REMOVAL
	EACH	EACH	EACH	FOOT	EACH	FOOT
RT STA 443+86.09 TO RT STA 444+36.09	1	1			0	0
RT STA 444+36.09 TO RT STA 446+11.09				175.0	3	77.75
RT STA 446+11.09 TO RT STA 446+42.34			1		1	31.25
RT STA 447+50.34 TO RT STA 447+81.59			1		1	31.25
RT STA 447+81.59 TO RT STA 448+69.09				87.5	1	77.75
RT STA 448+69.09 TO RT STA 449+19.09	1	1			0	0
LT STA 444+88.51 TO LT STA 445+38.51	1	1			0	0
LT STA 445+38.51 TO LT STA 446+26.01				87.5	1	77.75
LT STA 446+26.01 TO LT STA 446+57.26			1		1	31.25
LT STA 447+65.26 TO LT STA 447+96.51			1		1	31.25
LT STA 447+96.51 TO LT STA 449+71.51				175.0	3	77.75
LT STA 449+71.51 TO LT STA 450+21.51	1	1			0	0
TOTAL =	4	4	4	525	12	436

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY