

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	(1,2)RS-3	MOULTRIE	16	3
STA. 206+00		TO STA.238+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. / 20% STATE 1000
CODE NO	ITEM	UNIT		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	12	12
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5095	5095
40600300	AGGREGATE (PRIME COAT)	TON	102	102
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	323	323
40600990	TEMPORARY RAMP	SQ YD	54	54
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	4280	4280
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	66	66
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3408	3408
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	47217	47217
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	33	33
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	87	87
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	61	61
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	33	33
48101200	AGGREGATE SHOULDERS, TYPE B	TON	982	982
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	100	100
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	1	1
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. / 20% STATE 1000
CODE NO	ITEM	UNIT		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3984	3984
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45809	45809
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	230	230
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	130	130
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	664	664
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3230	3230
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	230	230
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	130	130
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	42579	42579
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	286	286
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4

\* SPECIALTY ITEMS

PLOT DATE = 12/11/2006  
 FILE NAME = c:\pro\mca\74226\481307\pa.dgn  
 PLOT SCALE = 50.0000 / 1 IN.  
 USER NAME = mcastrm

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.  
 DATE:                      DRAWN BY:                      CHECKED BY: