

| | | | | |
|---------------------|-----------|---------------|------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 762 | (1,2)RS-3 | MOULTRIE | 16 | 6 |
| STA. 206+00 | | TO STA.238+00 | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

RESURFACING SCHEDULE

| STATION TO STATION | LENGTH | AVERAGE PAVEMENT WIDTH | AREA | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | BITUMINOUS MATERIALS (PRIME COAT) | AGGREGATE (PRIME COAT) | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NTO | AGGREGATE SHOULDERS, TYPE B | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | TEMPORARY RAMP |
|---------------------------|--------|------------------------|---------|---|---|-----------------------------------|------------------------|--|-----------------------------|--|----------------|
| | | | | | | | | | | | |
| 207+00.00 TO 207+30.00 | 30.0 | 24.0 | 80.0 | 80.0 | 0.0 | 8.0 | 0.2 | 6.7 | 1.7 | 80.0 | 13.3 |
| 207+30.00 TO 232+28.50 | 2498.5 | 24.0 | 6662.7 | 6662.7 | 0.0 | 666.3 | 13.3 | 559.7 | 132.1 | 0.0 | 0.0 |
| 232+28.50 TO 232+58.50 | 30.0 | 24.0 | 80.0 | 0.0 | 0.0 | 8.0 | 0.2 | 6.7 | 1.7 | 80.0 | 13.3 |
| 232+58.50 TO 239+07.00 | 648.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 239+07.00 TO 239+37.00 | 30.0 | 24.0 | 80.0 | 0.0 | 0.0 | 8.0 | 0.2 | 6.7 | 1.7 | 80.0 | 13.3 |
| 239+37.00 TO 271+00.00 | 3163.0 | 24.0 | 8434.7 | 8434.7 | 0.0 | 843.5 | 16.9 | 708.5 | 174.4 | 0.0 | 0.0 |
| 271+00.00 TO 285+87.00 | 1487.0 | 25.0 | 4130.6 | 4130.6 | 0.0 | 413.1 | 8.3 | 347.0 | 81.7 | 0.0 | 0.0 |
| 285+87.00 TO 286+17.00 | 30.0 | 25.0 | 83.3 | 0.0 | 83.3 | 8.3 | 0.2 | 7.0 | 1.7 | 0.0 | 0.0 |
| 286+17.00 TO 295+80.00 | 963.0 | VAR | 29170.0 | 0.0 | 3241.1 | 324.1 | 6.5 | 272.3 | 28.0 | 0.0 | 0.0 |
| 295+80.00 TO 296+10.00 | 30.0 | 25.0 | 83.3 | 0.0 | 83.3 | 8.3 | 0.2 | 7.0 | 1.7 | 0.0 | 0.0 |
| 296+10.00 TO 340+96.00 | 4486.0 | 25.0 | 12461.1 | 12461.1 | 0.0 | 1246.1 | 24.9 | 1046.7 | 246.6 | 0.0 | 0.0 |
| 340+96.00 BK=341+00.00 AH | | | | | | | | | | | |
| 341+00.00 TO 396+90.00 | 5590.0 | 25.0 | 15527.8 | 15527.8 | 0.0 | 1552.8 | 31.1 | 1304.3 | 309.4 | 0.0 | 0.0 |
| 396+90.00 TO 397+20.00 | 30.0 | 25.0 | 83.3 | 0.0 | 0.0 | 8.3 | 0.2 | 7.0 | 1.7 | 83.3 | 13.9 |
| TOTALS | | | | 47217.0 | 3408.0 | 5095.0 | 102.0 | 4280.0 | 982.0 | 323.0 | 54.0 |

PAVEMENT MARKING SCHEDULE

| STATION TO STATION | LENGTH | PAINT PAVEMENT MARKING - LINE 4" | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | TEMPORARY PAVEMENT MARKING - LINE 4" | TEMPORARY PAVEMENT MARKING - LINE 6" | TEMPORARY PAVEMENT MARKING - LINE 12" | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SHORT-TERM PAVEMENT MARKING | WORK ZONE PAVEMENT MARKING REMOVAL | RAISED REFLECTIVE PAVEMENT MARKER |
|---------------------------|--------|----------------------------------|--|--|---|--|--------------------------------------|--------------------------------------|---------------------------------------|--|-----------------------------|------------------------------------|-----------------------------------|
| | | | | | | | | | | | | | |
| 207+00.00 TO 232+58.50 | 2558.5 | 5575.6 | 0.0 | 0.0 | 0.0 | 0.0 | 5575.6 | 0.0 | 0.0 | 0.0 | 512.0 | 85.3 | 32.0 |
| 232+58.50 TO 239+07.00 | 648.5 | 1459.1 | 0.0 | 0.0 | 0.0 | 0.0 | 1459.1 | 0.0 | 0.0 | 0.0 | 128.0 | 21.3 | 0.0 |
| 239+07.00 TO 280+77.23 | 4170.2 | 9183.0 | 0.0 | 0.0 | 0.0 | 0.0 | 9183.0 | 0.0 | 0.0 | 0.0 | 832.0 | 138.7 | 52.0 |
| 280+77.23 TO 285+77.23 | 500.0 | 1625.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1625.0 | 0.0 | 0.0 | 0.0 | 104.0 | 17.3 | 6.0 |
| 285+77.23 TO 286+17.23 | 40.0 | 80.0 | 80.0 | 0.0 | 0.0 | 0.0 | 160.0 | 0.0 | 0.0 | 0.0 | 8.0 | 1.3 | 6.0 |
| 286+17.23 TO 289+25.00 | 307.8 | 615.5 | 1231.9 | 0.0 | 58.2 | 0.0 | 1847.5 | 0.0 | 58.2 | 0.0 | 128.0 | 21.3 | 16.0 |
| 289+25.00 TO 290+40.00 | 115.0 | 85.0 | 230.0 | 115.0 | 0.0 | 46.8 | 315.0 | 115.0 | 0.0 | 46.8 | 48.0 | 8.0 | 12.0 |
| 290+40.00 TO 291+19.95 | 80.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 291+19.95 TO 292+34.95 | 115.0 | 85.0 | 230.0 | 115.0 | 0.0 | 46.8 | 315.0 | 115.0 | 0.0 | 46.8 | 48.0 | 8.0 | 12.0 |
| 292+34.95 TO 295+79.13 | 344.2 | 688.4 | 1377.8 | 0.0 | 71.3 | 0.0 | 2066.1 | 0.0 | 71.3 | 0.0 | 144.0 | 24.0 | 18.0 |
| 295+79.13 TO 296+19.13 | 40.0 | 80.0 | 80.0 | 0.0 | 0.0 | 0.0 | 160.0 | 0.0 | 0.0 | 0.0 | 8.0 | 1.3 | 6.0 |
| 296+19.13 TO 301+19.13 | 500.0 | 1625.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1625.0 | 0.0 | 0.0 | 0.0 | 104.0 | 17.3 | 6.0 |
| 301+19.13 TO 340+96.00 | 3976.9 | 8908.0 | 0.0 | 0.0 | 0.0 | 0.0 | 8908.0 | 0.0 | 0.0 | 0.0 | 792.0 | 132.0 | 50.0 |
| 340+96.00 BK=341+00.00 AH | | | | | | | | | | | | | 0.0 |
| 341+00.00 TO 397+20.00 | 5620.0 | 12569.0 | 0.0 | 0.0 | 0.0 | 0.0 | 12569.0 | 0.0 | 0.0 | 0.0 | 1128.0 | 188.0 | 70.0 |
| TOTALS | | 42579.0 | 3230.0 | 230.0 | 130.0 | 94.0 | 45809.0 | 230.0 | 130.0 | 94.0 | 3984.0 | 664.0 | 286.0 |

CLASS D PATCHING SCHEDULE

| LOCATION | CLASS D PATCHES | | | |
|------------|-----------------|------------------|------------------|-------------------|
| | TYPE I, 11 INCH | TYPE II, 11 INCH | TYPE II, 16 INCH | TYPE III, 16 INCH |
| | SQ YD | SQ YD | SQ YD | SQ YD |
| IL 32 (SB) | 16.7 | 33.3 | 30.7 | 0.0 |
| IL 32 (NB) | 16.7 | 53.3 | 30.7 | 32.7 |
| TOTALS | 33.0 | 87.0 | 61.0 | 33.0 |

GUARDRAIL SCHEDULE

| LOCATION | GUARDRAIL REMOVAL | | |
|-------------|--|---|----------------------------------|
| | TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT) | TRAFFIC BARRIER TERMINAL TYPE II, SPECIAL (TANGENT) | TERMINAL MARKER - DIRECT APPLIED |
| | FOOT | EACH | EACH |
| SN 070-0015 | | | |
| NW CORNER | 25.0 | 1.0 | 1.0 |
| NE CORNER | 25.0 | 1.0 | 1.0 |
| SW CORNER | 25.0 | 1.0 | 1.0 |
| SE CORNER | 25.0 | 1.0 | 1.0 |
| TOTALS | 100.0 | 4.0 | 4.0 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. / HORIZ.
 DATE / DRAWN BY / CHECKED BY

PLOT DATE = 12/11/2006
 FILE NAME = c:\pav\pav06\74226\rd\1307.paw.dgn
 USER NAME = msk1234