

SUMMARY OF QUANTITIES

F.A.I. RYER	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10	60-110.11185	MADISON	156	6
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	I000-2A 90% FED, 10% STATE RAODWAY	SFTY-2A 90% FED 10% STATE SN 060-0022	SFTY-2A 90% FED 10% STATE SN 060-0059	SFTY-2A 90% FED 10% STATE SN 060-0173	SFTY-2A 90% FED 10% STATE SN 060-0023	SFTY-2A 90% FED 10% STATE SN 060-0024	SFTY-2A 90% FED 10% STATE SN 060-0182	SFTY-2A 90% FED 10% STATE SN 060-0057	SFTY-2A 90% FED 10% STATE SN 060-0058	Y002-1C 100% STATE SIGNING	Y002-1C 90% FED 10% STATE SIGNING
CODE NO	ITEM	UNIT												
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	356	356										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16										
20200100	EARTH EXCAVATION	CU YD	15	15										
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	35	35										
20400800	FURNISHED EXCAVATION	CU YD	148	98				25	25					
25000200	SEEDING, CLASS 2	ACRE	0.8	0.8										
25100120	MULCH, METHOD 2	TON	1	1										
28100109	STONE RIPRAP, CLASS A5	SQ YD	5508					2551	2957					
28200200	FILTER FABRIC	SQ YD	5508					2551	2957					
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	83	83										
40600300	AGGREGATE (PRIME COAT)	TON	395	395										
40600555	LEVELING BINDER (HAND METHOD), N105	TON	100	100										
40600895	CONSTRUCTING TEST STRIP	EACH	2	2										
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	7155	7155										
40600990	TEMPORARY RAMP	SQ YD	1758	1449			36	118.5	118.5	36				
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	12334	12334										
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	45	45										
42001200	PAVEMENT FABRIC	SQ YD	274	274										
44000156	HOT-MIX ASPHALT SURFACE REMOVAL 1 3/4"	SQ YD	92680	92680										
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	3908	3908										
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4763	4763										
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	1323					622	701					
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1323					622	701					
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	40	40										
44004250	PAVED SHOULDER REMOVAL	SQ YD	2435	658				888	889					
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	357	357										
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	100	100										
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	173	173										
44213000	PATCHING REINFORCEMENT	SQ YD	40	40										
44213200	SAW CUTS	FOOT	3020	3020										
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3245	3245										
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	2435	658				888	889					
48203100	HOT-MIX ASPHALT SHOULDERS	TON	11,107	11,107										
50102400	CONCRETE REMOVAL	CU YD	27.1					14.9	12.2					
50104000	BRIDGE RAIL REMOVAL	FOOT	612					292	320					

PLOT DATE = 12/14/2086
 FILE NAME = c:\projects\76857\plan\p1\08765.dgn
 PLOT SCALE = 48.0000 / IN.
 REFERENCE = 4876

Rev.