

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(10,11)RS	MADISON	156	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

HOT-MIX ASPHALT SURFACE REMOVAL SCHEDULE				
LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	HOT MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
	SQ YD	SQ YD	SQ YD	SQ YD
RAMP G7				
0+66 TO 0+00		92		
0+00 TO 2+00		500		
2+00 TO 2+34		66		
2+34 TO 15+82		2396		265
WESTBOUND 270				
870+80 TO 877+20		853		510
EASTBOUND 70				
891+26 TO 899+83	1857			98
899+83 TO 902+00	627			
902+00 TO 903+74	474			
903+74 TO 917+00	3536			
917+00 TO 932+00	4000			
932+00 TO 947+00	4000			
947+00 TO 962+00	6750			
962+00 TO 965+00	883			
WESTBOUND 70				
901+06 TO 902+00	418			454
902+00 TO 903+50	708			
903+50 TO 911+00	1733			
915+13 TO 917+00	488			
917+00 TO 932+00	4000			
932+00 TO 945+33	3555			
945+33 TO 947+00	885			
947+00 TO 952+05	2693			
952+05 TO 962+00	4478			
962+00 TO 963+22	373			
963+22 TO 964+94	459			
FAI 70				
965+00 TO 980+00	8000			
980+00 TO 995+00	8000			
EB 70				
995+00 TO 996+00	267			359
997+49 TO 1010+00	3336			359
WB 70				
995+00 TO 995+85	227			359
997+47 TO 1010+00	3341			359
FAI 70				
1010+00 TO 1025+00	8000			
1025+00 TO 1030+65	3013			718
EASTBOUND 270				
861+08 TO 871+97	2904			975
874+61 TO 875+00	104			465
875+00 TO 888+21	3523			
WESTBOUND 270				
861+44 TO 875+00	3616			
875+00 TO 885+66	2843			
RAMP G1				
				231
RAMP G3				
				249
RAMP G5				
				116
RAMP G6				
				125
RAMP G4				
8+20 TO 16+00	1213			
16+00 TO 31+28	2377			246
EASTBOUND 70 UNDER RIGGIN ROAD				
			907.8	253.3
WESTBOUND 70 UNDER RIGGIN ROAD				
			886.7	253.3
EASTBOUND 70 UNDER STAUNTON ROAD				
			928.9	253.3
WESTBOUND 70 UNDER STAUNTON ROAD				
			1013.3	253.3
WESTBOUND 70 UNDER EASTBOUND 270				
			1026.7	253.3
TOTALS	92,680	3,908	4,763	7,155

PAVING SCHEDULE						
LOCATION	SHOULDER RUMBLE STRIPS	AGGREGATE (PRIME COAT)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE IL-19.0, N105	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE STONE MATRIX ASPHALT, N80	INCIDENTAL HOT-MIX ASPHALT SURFACING
	FOOT	TON	TON	TON	TON	TON
EASTBOUND 70						
891+26 TO 899+83		5.57	1.16	234.0	208.0	
899+83 TO 902+00		1.88	0.39	79.0	70.2	
902+00 TO 903+74		1.42	0.30	59.7	53.1	
903+74 TO 917+00		10.61	2.21	445.5	396.0	
917+00 TO 932+00		12.00	2.50	504.0	448.0	
932+00 TO 947+00		12.00	2.50	504.0	448.0	
947+00 TO 962+00		20.25	4.22	850.5	756.0	
962+00 TO 965+00		2.65	0.55	111.3	98.9	
WESTBOUND 70						
901+06 TO 902+00		1.25	0.26	52.6	46.8	
902+00 TO 903+50		2.13	0.44	89.3	79.3	
903+50 TO 911+00		5.20	1.08	218.4	194.1	
915+13 TO 917+00		1.46	0.31	61.5	54.7	
917+00 TO 932+00		12.00	2.50	504.0	448.0	
932+00 TO 945+33		10.66	2.22	447.9	398.1	
945+33 TO 947+00		2.66	0.55	111.6	99.2	
947+00 TO 952+05		8.08	1.69	339.4	301.7	
952+05 TO 962+00		13.43	2.80	564.2	501.5	
962+00 TO 963+22		1.12	0.23	47.0	41.8	
963+22 TO 964+94		1.38	0.29	57.8	51.4	
FAI 70 - EASTBOUND & WESTBOUND						
965+00 TO 980+00		24.00	5.01	1008.0	896.0	
980+00 TO 995+00		24.00	5.01	1008.0	896.0	
MEDIAN CROSS OVER						
983+16						45.0
EASTBOUND ONLY						
995+00 TO 996+00		0.80	0.17	33.6	29.9	
997+49 TO 1010+00		10.01	2.09	420.3	373.6	
WESTBOUND ONLY						
995+00 TO 995+85		0.68	0.14	28.6	25.4	
997+47 TO 1010+00		10.02	2.09	421.0	374.2	
FAI 70 - EASTBOUND & WESTBOUND						
1010+00 TO 1025+00		24.00	5.01	1008.0	896.0	
1025+00 TO 1030+65		9.04	1.89	379.7	337.5	
EASTBOUND 270						
861+08 TO 871+97		8.71	1.82	365.9	325.2	
874+61 TO 875+00		0.31	0.07	13.1	11.6	
875+00 TO 888+21		10.57	2.20	443.9	394.5	
WESTBOUND 270						
861+44 TO 875+00		10.85	2.26	455.6	405.0	
875+00 TO 885+66		8.53	1.78	358.2	318.4	
870+80 TO 877+20		2.56	0.53	143.4		
RAMP G1						
2+72 TO 5+30		1.12	0.23		83.5	
5+30 TO 5+90		0.21	0.04		15.7	
5+90 TO 7+00		0.40	0.08		30.1	
7+00 TO 16+88		3.62	0.76		270.5	
RAMP G3						
7+00 TO 20+50		3.60	0.75		268.8	
RAMP G4						
8+20 TO 16+00		3.64	0.76	152.9	135.9	
16+00 TO 31+28		7.13	1.49	299.5	266.2	
RAMP G5						
25+53 TO 20+00		1.29	0.27		96.3	
20+00 TO 6+82		3.08	0.64		229.6	
6+82 TO 5+30		0.43	0.09		32.2	
5+30 TO 3+00		0.69	0.14		51.5	
3+00 TO 0+00		0.48	0.10		35.5	
RAMP G6						
1+78 TO 2+11		0.10	0.02		7.2	
2+11 TO 9+71		2.03	0.42		151.3	
9+71 TO 10+76		0.29	0.06		21.6	
10+76 TO 12+67		0.49	0.10		36.8	
12+67 TO 13+15		0.16	0.03		11.6	
RAMP G7						
-0+66 TO 0+00		0.28	0.06	15.4	10.3	
0+00 TO 2+00		1.50	0.31	84.0	56.0	
2+00 TO 2+34		0.20	0.04	11.1	7.4	
2+34 TO 15+82		3.59	1.50	402.6	268.4	
TOTALS	84476	304.2	64.2	12334.2	12064.5	45.0

PRIME PAY ITEMS IN THIS SCHEDULE AND THE HMA SHOULDER SCHEDULE ARE COMBINED IN THE SQO

PLOT DATE = #DATE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULES FAI ROUTE 70 SECTION 60-(10,11)RS MADISON COUNTY
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY