

SUMMARY OF QUANTITIES

EXP. DATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	94-F3000-06-BT	COOK	105	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	83709	STPE-0001(479)	

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	BIKE PATH Y052-TEA	SIGNING Y002-1C	SIGNAL Y031-1F		
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,506	2,506				
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	266	266				
20101000	TEMPORARY FENCE	FOOT	27,215	27,215				
20200100	EARTH EXCAVATION	CU YD	6,885	6,885				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	439	439				
20400800	FURNISHED EXCAVATION	CU YD	4,726	4,726				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	107	107				
20800150	TRENCH BACKFILL	CU YD	86	86				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	860	860				
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	7,745	7,745				
25000312	SEEDING, CLASS 4A	ACRE	5.50	5.50				
* 25000314	SEEDING, CLASS 4B	ACRE	0.30	0.30				
* 25000400	NITROGEN FERTILIZER NUTRIENT	LB	640	640				
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LB	640	640				
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	640	640				
* 25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	1.30	1.30				
* 25002300	TEMPORARY SEEDING	ACRE	4.00	4.00				
* 25100630	EROSION CONTROL BLANKET	SQ YD	1,500	1,500				
* 28000300	TEMPORARY DITCH CHECKS	EACH	3	3				
28000400	PERIMETER EROSION BARRIER	FOOT	48,800	48,800				
28000500	INLET AND PIPE PROTECTION	EACH	32	32				
* 28000720	MULCH, METHOD 2	ACRE	7.10	7.10				
28100107	STONE RIPRAP, CLASS A4	SQ YD	33	33				
28200200	FILTER FABRIC	SQ YD	33	33				
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	34,150	34,150				
40600100	BITUMINOUS MATERIAL, PRIME COAT	GALLON	3,640	3,640				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	120	120				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3,956	3,956				
42001300	PROTECTIVE COAT	SQ YD	313	313				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	790	790				
42400800	DETECTABLE WARNINGS	SQ FT	150	150				
44000100	PAVEMENT REMOVAL	SQ YD	366	366				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	111	111				
44000600	SIDEWALK REMOVAL	SQ FT	100	100				
50102400	CONCRETE REMOVAL	CU YD	0.8	0.8				
* 50105220	PIPE CULVERT REMOVAL	FOOT	36	36				
50200100	STRUCTURE EXCAVATION	CU YD	67	67				
50300225	CONCRETE STRUCTURES	CU YD	4.0	4.0				
50800205	REINFORCEMENT BARS, EPOXY COATED	LB	260	260				
50800515	BAR SPlicERS	EACH	25	25				
* 50901725	BICYCLE RAILING, SPECIAL	FOOT	170	170				
54001000	BOX CULVERT END SECTIONS	EACH	2	2				
54010803	PRECAST CONCRETE BOX CULVERT 8' X 3'	FOOT	50	50				
54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	39	39				
54200427	PIPE CULVERTS, TYPE 1 RCCP 12"	FOOT	146	146				
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	101	101				
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	204	204				
54207159	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	36	36				
54207165	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	FOOT	38	38				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	8	8				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION 15"	EACH	6	6				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	EACH	14	14				
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2				
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	4	4				
* 60109582	PIPE UNDERDRAINS FOR STRUCTURES, 6"	FOOT	228	228				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4				

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	BIKE PATH Y052-TEA	SIGNING Y002-1C	SIGNAL Y031-1F		
* 60226400	MANHOLES, DROP TYPE, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	FOOT	28	28				
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FOOT	807	807				
63200310	GUARDRAIL REMOVAL	FOOT	200	200				
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1				
* 66410410	CHAIN LINK FENCE TO BE RELOCATED	FOOT	400	400				
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6				
* 67100100	MOBILIZATION	L SUM	1	1				
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1				
* 72000100	SIGN PANEL TYPE 1	SQ FT	292		292			
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6		6			
72900100	METAL POST - TYPE A	FOOT	844		844			
* 78001100	PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	173	173				
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	31,573	31,573				
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	31	31				
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	841	841				
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	1,400	1,400				
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	25	25				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	50	50				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	6			6		
* 81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	6			6		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	345			345		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	357			357		
* 87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	1			1		
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4			4		
* 87900200	DRILL EXISTING HANDHOLE	EACH	1			1		
* 88100200	PEDESTRIAN SIGNAL HEAD, 1-FACE, BRACKET MOUNTED	EACH	3			3		
* 88100600	PEDESTRIAN SIGNAL HEAD, 3-FACE, BRACKET MOUNTED	EACH	1			1		
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	5			5		
* 89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	2			2		
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1			1		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1		
* A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALLED AND BURLAPED	EACH	73	73				
* A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPED	EACH	73	73				
* A2006708	TREE, QUERCUS MACROCARPA (BUR OAK), 1" CALIPER, BALLED AND BURLAPED	EACH	73	73				
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPED	EACH	73	73				
* D2002996	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 10' HEIGHT, BALLED AND BURLAPED	EACH	13	13				
* X0301059	BLOCK RETAINING WALL	SQ FT	460	460				
* X0321322	DROP GATE	EACH	8	8				
* X5121800	PERMANENT STEEL SHEET PILING	SQ FT	2,660	2,660				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	20	20				
* XX000882	WOOD FENCE	FOOT	1014	1014				
* XX003437	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTION	EACH	2	2				
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
* Z0062300	SAWING ASPHALT SURFACE	FOOT	30	30				
* XY006822	TRAIL HEAD MAP	EACH	1	1				
* XY006823	CONCRETE BARRIERS	EACH	15	15				
* X0696100	PARKING BLOCKS	EACH	22	22				

* DENOTES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE 3/31/06
DRAWN BY RTA
CHECKED BY SMH

revised 2/23/07