

EARTHWORK SCHEDULE

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94-F3000-06-BT	COOK	105	7
STA.	TO STA.		
VDL ROAD DIST. NO.	ILLINOIS	83709	STPE-D001(479)

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAUL DOUGLAS TRAIL (Continued)									
157+00	158+00	2		2	70	-68	26	16	10
158+00	159+00	11		9	3	6	20	8	12
159+00	160+00	9		8	20	-12	21	9	12
160+00	161+00	53		45	20	25	25	15	10
161+00	161+73	39		33	2	31	17	9	8
161+73	162+00	0		0	13	-13	6	3	3
162+00	163+00	0		0	197	-197	35	26	9
163+00	164+00	10		9	193	-185	45	38	7
164+00	165+00	18		15	74	-59	42	35	8
165+00	166+00	14		12	35	-23	29	20	9
166+00	167+00	26		22	4	18	22	12	11
167+00	168+00	27		23	2	21	22	10	12
168+00	169+00	23		20	10	10	25	15	10
169+00	170+00	53		45	41	4	42	35	8
170+00	171+00	62		53	51	2	47	39	8
171+00	172+00	43		37	34	3	38	29	9
172+00	173+00	38		32	21	11	34	24	10
173+00	174+00	57		48	10	38	31	22	9
174+00	174+94	77		65	8	57	33	21	12
174+94	175+00	3		3	0	3	1	1	0
175+00	176+00	18		15	77	-62	29	20	9
176+00	177+00	18		15	97	-82	32	19	13
177+00	178+00	0		0	158	-158	35	23	12
178+00	179+00	6		5	62	-57	26	14	12
179+00	180+00	6		5	56	-51	24	12	12
180+00	181+00	1		1	173	-172	32	21	11
181+00	182+00	1		1	162	-161	31	21	10
182+00	183+00	5		4	46	-42	23	11	12
183+00	184+00	8		7	3	4	19	8	11
184+00	185+00	8		7	14	-7	21	9	12
185+00	186+00	18		15	13	2	22	10	12
186+00	187+00	21		18	1	17	19	8	11
187+00	188+00	3		3	12	-9	20	9	11
188+00	189+00	5		4	11	-7	20	8	12
189+00	190+00	14		12	0	12	18	6	12
190+00	191+00	13		11	2	9	18	8	10
191+00	192+00	5		4	8	-4	20	9	11
192+00	193+00	12		10	6	4	20	8	12
193+00	194+00	17		14	1	13	19	7	12
194+00	195+00	8		7	5	2	20	8	12
195+00	196+00	11		9	6	3	20	9	11
196+00	197+00	36		31	1	30	21	10	11
197+00	198+00	46		39	0	39	22	10	12
198+00	199+00	27		23	0	23	20	8	12
199+00	200+00	18		15	0	15	18	7	11
200+00	201+00	16		14	0	14	17	7	10
201+00	202+00	8		7	6	1	19	8	11
202+00	203+00	9		8	6	2	20	8	12
203+00	204+00	9		8	13	-5	20	9	11
204+00	205+00	8		7	13	-6	19	8	11
205+00	206+00	17		14	0	14	17	7	10
206+00	206+25	3		3	0	3	4	2	2
206+25	207+00	6		5	3	2	15	6	9
207+00	208+00	17		14	3	11	21	9	12
208+00	209+00	19		16	2	14	20	9	11
209+00	210+00	14		12	2	10	20	8	12
210+00	211+00	7		6	18	-12	21	10	11
211+00	212+00	2		2	18	-16	21	9	12
212+00	213+00	8		7	2	5	18	7	11
213+00	214+00	16		14	2	12	19	8	11
214+00	215+00	15		13	2	11	19	7	12
215+00	216+00	65		55	1	54	24	12	13
216+00	216+20	12		10	3	7	5	3	2
216+20	216+40	0		0	28	-28	6	4	2
216+40	216+60	0		0	44	-44	7	4	3
216+60	216+80	8		7	25	-18	6	4	2

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAUL DOUGLAS TRAIL (Continued)									
216+80	217+00	25		21	5	16	6	4	2
217+00	217+04	8		7	0	7	1	1	0
217+04	217+20	28		24	0	24	5	3	2
217+20	217+40	25		21	11	10	7	5	2
217+40	217+60	8		7	27	-20	6	3	3
217+60	217+80	0		0	31	-31	5	3	2
217+80	218+00	0		0	18	-18	5	3	2
218+00	219+00	0		0	77	-77	27	15	12
219+00	220+00	0		0	79	-79	26	14	12
220+00	221+00	19		16	17	-1	22	10	12
221+00	222+00	76		65	0	65	26	15	11
222+00	223+00	60		51	2	49	24	14	10
223+00	223+56	2		2	13	-11	11	6	5
223+56	224+00	13		11	9	2	10	6	4
224+00	225+00	41		35	0	35	21	9	12
225+00	226+00	37		31	0	31	21	9	12
226+00	227+00	51		43	0	43	24	13	11
227+00	228+00	34		29	0	29	22	10	12
228+00	229+00	27		23	0	23	20	8	12
229+00	230+00	244		207	0	207	35	26	9
230+00	231+00	282		240	0	240	39	31	8
231+00	232+00	58		49	368	-319	45	38	7
232+00	233+00	0		0	397	-397	43	35	9
233+00	234+00	16		14	31	-17	25	14	11
234+00	235+00	33		28	9	19	27	17	10
235+00	236+00	42		36	9	27	28	18	10
236+00	237+00	25		21	13	8	24	14	10
237+00	238+00	7		6	12	-6	21	9	12
238+00	239+00	28		24	1	23	20	9	11
239+00	240+00	32		27	0	27	20	9	11
240+00	241+00	32		27	0	27	20	9	11
241+00	242+00	20		17	22	-5	23	12	12
242+00	243+00	28		24	22	2	24	13	11
243+00	244+00	50		43	0	43	22	10	12
244+00	245+00	21		18	370	-352	43	36	7
245+00	246+00	0		0	572	-572	57	52	5
246+00	247+00	12		10	201	-191	34	25	9
247+00	248+00	14		12	13	-1	22	12	11
248+00	249+00	2		2	56	-54	26	16	10
249+00	250+00	0		0	50	-50	24	14	10
250+00	251+00	128		109	7	102	29	20	9
251+00	252+00	259		220	0	220	38	30	8
252+00	253+00	139		118	0	118	29	18	11
253+00	254+00	9		8	23	-15	21	10	11
254+00	255+00	29		25	23	2	23	13	10
255+00	256+00	29		25	22	3	23	13	10
256+00	257+00	16		14	22	-8	22	12	11
257+00	258+00	40		34	0	34	21	9	12
258+00	259+00	24		20	5	15	21	9	12
259+00	260+00	0		0	94	-94	28	17	11
260+00	261+00	0	34	0	233	-233	37	22	15
261+00	261+50	0		0	103	-103	17	9	8
261+50	262+00	0		0	52	-52	14	8	6
262+00	262+50	1		1	40	-39	13	7	6
262+50	263+00	0		0	47	-47	15	8	7
263+00	263+50	0		0	63	-63	16	10	6
263+50	264+00	0		0	83	-83	17	12	6
264+00	264+50	0		0	83	-83	17	9	8
264+50	265+00	0		0	84	-84	17	10	7

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

EARTHWORK
SCHEDULE

SCALE NONE
DATE 3/29/06
DRAWN BY RTA
CHECKED BY SMH

revised 2/23/07