

ESTIMATED BILL OF MATERIAL	S	
PAY ITEM	UNIT	QUANTITY
TEMPORARY WOOD POLE (CLASS 5 OR BETTER) 45 FOOT MINIMUM	EACH	- 4
FULL-ACTUATED CONTROLLER AND TEMPORARY CABINET	EACH	1
SPAN WIRE	FOOT	591
TETHER WIRE	FOOT	502
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	208
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	646
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	1273
ELECTRIC CABLE AERIAL SUSPENDED, COMMUNICATION, NO. 16 5 1/2 PAIR	FOOT	707
ELECTRIC CABLE AERIAL SUSPENDED, SERVICE, NO. 6 2C	FOOT	120
ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	208
SIGNAL HEAD, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	4
SIGNAL HEAD, 1-FACE, 5-SECTION, SPAN WIRE MOUNTED	EACH	8
LIGHT DETECTOR	EACH	2
LIGHT DETECTOR AMPLIFIER	EACH	1
VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)	EACH	1
SERVICE INSTALLATION - POLE MOUNTED	EACH	1

I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS					TOTAL WATTAGE
TYPE	NO. LAMPS:	WATT		X OPERATION	WATTAGE
SIGNAL (RED)	12	135		0.50	810
(YELLOW)	12	135		0.25	405
(GREEN)	12	135		0.25	405
ARROW	16	135		0.10	216
CONTROLLER	1	100		1.00	100
VIDEO SYSTEMS	11	150		1.00	150
	1		-		
	-				
FLASHER				0.50	
				TOTAL =	2086
ENERGY COSTS TO	901 WELL ELK GROV CONTACT: PHONE:	INGTON A E VILLAC JUDITH	VENUE SE, IL SCHOME		

COMPANY: COM ED

