## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)

UNLESS OTHERWISE SHOWN.

REVISIONS

NAME DATE
R. MIRS 9-15-97
R. MIRS 12-11-97
T. RAMMACHER 2-2-99

DRAWN BY: BUR. OF DESIGN
03/13/00 CHECKED BY

Mon Mar 13 13:56:11 2000

\\dlcaddl\projects\diststd\tc22.dgn LV=35

TC22