

SUMMARY OF QUANTITIES

IDOT ITEMS	ITEMS	UNIT	CHURCH ROAD		GREEN STREET		PROJECT TOTALS		
			(500 1) 1000-2A QUANTITY	NON-PARTICIPATING QUANTITY	(500 2) 1000-2A QUANTITY	NON-PARTICIPATING QUANTITY	1000-2A QUANTITY	NON-PARTICIPATING QUANTITY	TOTAL QUANTITY
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SY	120	0	314	0	434	0	434
*25200110	SODDING, SALT TOLERANT	SY	120	0	314	0	434	0	434
25200200	SUPPLEMENTAL WATERING	UNIT	5	0	10	0	15	0	15
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SY	190	0	0	0	190	0	190
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	100	0	100	0	200	0	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	455	0	1100	0	1555	0	1555
40600300	AGGREGATE (PRIME COAT)	TON	10	0	20	0	30	0	30
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	210	0	500	0	710	0	710
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	436	0	1000	0	1436	0	1436
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SY	130	0	11	0	141	0	141
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SF	0	0	2300	0	2300	0	2300
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SY	0	0	192	0	192	0	192
44000200	DRIVEWAY PAVEMENT REMOVAL	SY	4641	0	10909	0	15550	0	15550
42400800	DETECTABLE WARNINGS	SF	320	0	68	0	388	0	388
44000600	SIDEWALK REMOVAL	SF	0	0	2300	0	2300	0	2300
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	0	630	0	880	0	880
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SY	4641	0	10909	0	15550	0	15550
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	0	0	3	0	3	0	3
67100100	MOBILIZATION	L SUM	0.5	0	0.5	0	1	0	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	0.5	0	0.5	0	1	0	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	0.5	0	0.5	0	1	0	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	0.5	0	0.5	0	1	0	1
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SF	230	0	50	0	280	0	280
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2250	0	6100	0	8350	0	8350
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	335	0	1850	0	2185	0	2185
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	32	0	200	0	232	0	232
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80	0	220	0	300	0	300
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	280	0	330	0	610	0	610
X0300624	RAILROAD PROTECTIVE LIABILITY INSURANCE (SPECIAL)	EACH	1	0	0	0	1	0	1
XX000667	SUB-BASE GRANULAR MATERIAL, TYPE B 2"	SY	0	0	256	0	256	0	256
XX003535	AGGREGATE BASE COURSE, TYPE B, 2"	SY	130	0	11	0	141	0	141
*Z0017500	DRAINAGE & UTILITY STRUCTURE ADJUSTMENT (SPECIAL)	EACH	25	0	75	0	100	0	100
XX006786	CLASS D PATCHES, SPECIAL, 7-INCHES	SY	455	0	1100	0	1555	0	1555

• SPECIALTY ITEMS

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_  
 DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_

**CHRISTOPHER B. BURKE** ENGINEERING LTD., PLAN  
 9575 West Higgins Road, Suite 600  
 Rosemont, Illinois 60018  
 (847) 823-0500



DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_  
 DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES AND STORM SEWER SCHEDULE

SCALE NTS  
 DATE 12/20/2006

DRAWN BY JCR  
 CHECKED BY LMF