



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 28, 2012

SUBJECT: Algonquin Road
Section 18A-1
McHenry County
Contract No. 60F78
Item No. 121, March 29, 2012 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions.
2. Revised pages 14 & 15 of the Special Provisions.
3. Deleted pages 139 – 151 of the Special Provisions.
4. Revised sheets 2 & 5 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P. E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:ks

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF IMPROVEMENT.....	1
COMPLETION DATE PLUS WORKING DAYS.....	1
MAINTENANCE OF ROADWAYS.....	2
STATUS OF UTILITIES TO BE ADJUSTED	2
EMBANKMENT I.....	3
EMBANKMENT STABILITY.....	4
TOPSOIL FURNISH AND PLACE, 4".....	4
RECLAIMED ASPHALT PAVEMENT AND SHINGLES (D-1)	5
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1).....	13
BITUMINOUS PRIME COAT FOR HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) (D-1).....	14
CONCRETE THRUST BLOCK.....	14
TRAFFIC CONTROL PLAN.....	16
BUILDING REMOVAL – CASE IV (NO ASBESTOS).....	16
STABILIZED CONSTRUCTION ENTRANCE	18
DEWATERING.....	18
EXPLORATION TRENCH, SPECIAL	19
SEEDING, CLASS 4B (MODIFIED).....	19
EROSION CONTROL BLANKET (SPECIAL).....	20
CONCRETE ANCHORS.....	20
STORM SEWERS TO BE CLEANED.....	21
CATCH BASINS, TYPE A, 5'- DIAMETER, WITH SPECIAL FRAME AND GRATE.....	21
DUST CONTROL, SPECIAL	21
TEMPORARY DITCH CHECKS (SPECIAL)	22
METAL TRUSS REMOVAL	22
CONCRETE BLOCK REMOVAL.....	23
DETENTION BASIN OUTLET STRUCTURE.....	23
POLYMER TABLETS.....	23
TRIPAM POLYMER.....	24
MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	25
AGREEMENT TO PLAN QUANTITY (BDE).....	25
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	26
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)	27
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)	28
DIGITAL TERRAIN MODELING FOR EARTHWORK CALCULATIONS (BDE).....	30
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	31
FRICTION AGGREGATE (BDE)	39

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)	41
METAL HARDWARE CAST INTO CONCRETE (BDE).....	42
PAVEMENT PATCHING (BDE).....	43
PAYMENTS TO SUBCONTRACTORS (BDE)	43
PAYROLLS AND PAYROLL RECORDS (BDE).....	44
PORTLAND CEMENT CONCRETE (BDE)	45
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE)	79
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	90
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....	90
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	91
TEMPORARY EROSION AND SEDIMENT CONTROL (BDE).....	92
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE).....	92
UTILITY COORDINATION AND CONFLICTS (BDE).....	92
WARM MIX ASPHALT (BDE)	97
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	102
PROJECT LABOR AGREEMENT	106
STORM WATER POLLUTION PREVENTION PLAN.....	119
IEPA PERMITS	129
SEDIMENT TRAP	132

Revised 2/28/12

BITUMINOUS PRIME COAT FOR HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) (D-1)

Effective: May 1, 2007

Revise Article 407.06(b) of the Standard Specifications to read:

“A bituminous prime coat shall be applied between each lift of HMA according to Article 406.05(b) at a rate of 0.02 to 0.05 gal/sq yd (0.1 to 0.2 L/sq m), the exact rate to be determined by the Engineer.”

Revise the second paragraph of Article 407.12 of the Standard Specifications to read:

“Prime Coat will be paid for at the contract unit price per gallon (liter) or per ton (metric ton) for BITUMINOUS MATERIALS (PRIME COAT).”

CONCRETE THRUST BLOCK

Description. This work shall consist of constructing cast-in-place concrete thrust blocks on slope drains as shown on the plan details.

Materials. The concrete shall be Class SI in accordance with Section 1020 of the Standard Specifications.

Method of Measurement. This work will be measured for payment as individual items and the unit of measurement will be each.

Basis of Payment. This work will be paid for at the contract unit price per each for CONCRETE THRUST BLOCK.

Revised 20/28/12

Page intentionally left blank.

Revised 20/28/12

Deleted Pages 139-151 2/28/2012