

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE 0021

URBAN
TOTAL
QUANTITIES

100%
STATE

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	100% STATE					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	304	304					
25200110	SODDING, SALT TOLERANT	SQ YD	304	304					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	83	83					
42001300	PROTECTIVE COAT	SQ YD	3057	3057					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	38	38					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	20327	20327					
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	930	930					
42400800	DETECTABLE WARNINGS	SQ FT	230	230					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	38	38					
44000600	SIDEWALK REMOVAL	SQ FT	21257	21257					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	406	406					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2436	2436					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	309	309					

FILE NAME =	USER NAME = curryw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\curryw\02882135\0162011-est-plan.dgn		DRAWN -	REVISED -			VARIOUS	2011-075-1	COOK	13	3	
PLOT SCALE = 3/8" = 1' / m		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 60P99			
PLOT DATE = 1/10/2012		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					