

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-075-I	COOK	13	4

CONTRACT: 60P99

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 6' PARALLEL	SIDEWALK 8" R&R (SQFT) 6' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
Entire 5700 Block of West 63rd Place	600.0	100.0	51.5	0.0	435.0	0.0	0.0	10.0	Replace 600 Feet of Curb on the South Side of Boulevard
Entire 5800 Block of West 63rd Place	600.0	100.0	66.7	0.0	300.0	0.0	0.0		Replace 600 Feet of Curb on the South Side of Boulevard
Entire 5900 Block of West 63rd Place	600.0	100.0	100.0	0.0	0.0	0.0	0.0		Replace 600 Feet of Curb on the South Side of Boulevard
3823 West 63rd Place		0.0	0.0	0.0	180.0	0.0	0.0		Replace 5-6 Sidewalk Squares and Courtesy Walk
5532 West 63rd Place		0.0	0.0	9.0	0.0	0.0	0.0		Replace 2 Courtesy Walk Squares - WANTS SLOPE/INCLINE
6031 West 63rd Place		0.0	0.0	45.0	0.0	0.0	0.0		Replace Courtesy Walk & Carriage Walk
3738 West 63rd Street		0.0	0.0	0.0	30.0	0.0	0.0		Replace 1 Sidewalk Square
4120 West 63rd Street		0.0	0.0	0.0	120.0	0.0	0.0		Replace 4 Sidewalk Squares - In Parkway - Raised About 1'6" Feet High From Adjacent Tree Roots
6559 South Kilbourn Avenue	15.0	2.5	0.0	0.0	0.0	0.0	25.0		Replace Driveway Apron and Adjacent Curb Around Perimeter of Driveway on 66th Street Side
5626 South Kilbourn Avenue		0.0	0.0	22.5	0.0	0.0	0.0		Replace Courtesy Walk directly in front of home
5626 South Kilbourn Avenue		0.0	0.0	30.0	0.0	0.0	0.0		Replace Courtesy Walk leading to the gangway
6645 South Kilbourn Avenue		0.0	0.0	0.0	60.0	0.0	0.0		Replace 2 Sidewalk Squares
4500 West 66th Place		0.0	0.0	22.5	1110.0	0.0	0.0	40.0	Replace 28 Side Sidewalk Squares, 2 Side Courtesy Walk Squares, 9 Front Sidewalk Squares, 5 Front Courtesy Walk Squares, and 4 ADA Ramps
3825 West 66th Place		0.0	0.0	0.0	270.0	0.0	0.0		Replace 8-9 Sidewalk Squares
4508 West 66th Place		0.0	0.0	0.0	0.0	0.0	0.0		Replace cracked curb. There is also a standing water issue
4501 West 66th Street		0.0	0.0	27.0	600.0	180.0	0.0	40.0	Replace 26 Side Sidewalk Squares, 6 Side Courtesy Walk Squares, 9 Front Sidewalk Squares, and 4 ADA Ramps
4524 West 65th Place		0.0	0.0	0.0	240.0	0.0	0.0		Replace 8 Sidewalk Squares
3607 West 65th Street		0.0	0.0	0.0	120.0	0.0	0.0		Replace 4 Sidewalk Squares
3645 West 62nd Street		0.0	0.0	0.0	120.0	0.0	0.0		Replace 4 Sidewalk Squares - Broken Concrete
3655 West Marquette Road		0.0	0.0	0.0	30.0	0.0	0.0		Replace 1 Sidewalk Square - Adjacent Squares
3659 West Marquette Road		0.0	0.0	0.0	30.0	0.0	0.0		Replace 1 Sidewalk Square - Adjacent Squares
3758 West 60th Place		0.0	0.0	0.0	210.0	0.0	0.0		Replace 5-7 Sidewalk Squares - All On Hamlin Avenue Side
3935 West 60th Place		0.0	0.0	0.0	30.0	0.0	0.0		Replace 1 Sidewalk Square Located In Front Of Gangway
3811 West 60th Place		0.0	0.0	0.0	210.0	0.0	0.0		Replace 6-7 Sidewalk Squares
3804 West 61st Street		0.0	0.0	0.0	60.0	0.0	0.0		Replace 1-2 Sidewalk Squares
3824 West 61st Street		0.0	0.0	0.0	270.0	0.0	0.0		Replace 9 Sidewalk Squares
3901 West 61st Street									Replace 2 Sidewalk Squares Adjacent to ADA Ramps
3811 West 70th Place		0.0	0.0	0.0	180.0	0.0	0.0		Replace 6 Sidewalk Squares
3818 West 70th Place		0.0	0.0	22.5	180.0	0.0	0.0		Replace 6 Sidewalk Squares & Courtesy Walk
3813 West 58th Place				22.5					Replace Courtesy Walk
SUB-TOTAL	1815.0	302.5	218.2	201.0	4785.0	180.0	25.0	90.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES