

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-075-I	COOK	13	6

CONTRACT: 60P99

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 6' PARALLEL	SIDEWALK 8" R&R (SQFT) 6' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
6323 West 64th Street		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares
4517 West 65th Place	9.0	1.5	1.5	0.0	0.0	0.0	0.0		Replace curb gutter. Too deep causing standing water
4530 West 65th Place	5.0	0.9	0.0	7.5	0.0	0.0			Replace 5 feet of Curb In Front of Sewer
4539 West 65th Place	40.0	6.7	5.9	0.0	0.0	0.0	10.0		Replace 40 Feet of Curb & Gutter
6317-6319 West 64th Place		0.0	0.0	0.0	390.0	30.0	30.0		Replace 14 Sidewalk Squares, 1 Square Above Driveway Apron, and 1 Driveway Apron
4615 West 79th Place		0.0	0.0	0.0	120.0	0.0			Replace 4 Sidewalk Squares
4622 West 82nd Street		0.0	0.0	0.0	60.0	0.0			Replace 2 Sidewalk Squares
5514 South Kolmar Avenue		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares
5518 South Kolmar Avenue		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares cracked in front parkway
5724 South Kostner Avenue		0.0	0.0	0.0	120.0	0.0			Replace 4 Sidewalk Squares
5730 South Kostner Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Sidewalk Squares
5802 South Kostner Avenue		0.0	0.0	9.0	210.0	0.0			Replace 6-7 Sidewalk Squares & 2 Courtesy Walk Squares
6405 South Kostner Avenue		0.0	0.0	22.5	0.0	0.0			Replace Courtesy Walk
5524 South Kolin Avenue		0.0	0.0	15.0	0.0	0.0			Replace 2 Carriage Walk Squares
6401 South Kolin Avenue		0.0	0.0	0.0	180.0	0.0			Replace 2-6 Sidewalk Squares
6418 South Kolin Avenue		0.0	0.0	0.0	120.0	0.0			Replace 4 Sidewalk Squares
6422 South Kolin Avenue		0.0	0.0	22.5	90.0	0.0			Replace 3 Sidewalk Squares & Courtesy Walk
5601 South Karlov Avenue		0.0	0.0	9.0	930.0	0.0		40.0	Replace 26 Side Sidewalk Squares, 5 Front Sidewalk Squares, 4 ADA Ramp Squares, 2 Catwalk Squares, 1 Side Driveway Apron
6007 South Kildare Avenue		0.0	0.0	0.0	30.0	0.0			Replace 1 Sidewalk Square
5743 South Kenneth Avenue	2.0	0.4	0.0	3.0	0.0	0.0			Replace 2 Feet of Broken Curb Adjacent To Street Light Pole
5744 South Kenneth Avenue	5.0	0.9	0.0	7.5	0.0	0.0			Replace 5 Feet of Broken Curb Adjacent To Curblin Sewer
5748 South Kenneth Avenue	3.0	0.5	0.0	4.5	0.0	0.0			Replace 3 Feet of Cracked Curb
5749 South Kenneth Avenue	3.0	0.5	0.0	4.5	0.0	0.0			Replace 1 Foot of Cracked Curb Adjacent To Curblin Sewer
5745 South Tripp Avenue		0.0	0.0	4.5	240.0	0.0			Replace 8 Sidewalk Squares & 3 Courtesy Walk Squares
5749 South Tripp Avenue		0.0	0.0	4.5	240.0	0.0			Replace 8 Sidewalk Squares & 3 Courtesy Walk Squares
5753 South Tripp Avenue		0.0	0.0	4.5	240.0	0.0			Replace 8 Sidewalk Squares & 3 Courtesy Walk Squares
6447 South Tripp Avenue					210.0				Replace 6-7 Sidewalk Squares
8135 South Tripp Avenue		0.0	0.0	0.0	270.0	0.0			Replace 9 Raised/Cracked Sidewalk Squares
5936 South Major Avenue		0.0	0.0	0.0	30.0	0.0			Replace 1 Sidewalk Square
5958 South Major Avenue				9.0	0.0				Replace Curb Facing 60th Street Near Courtesy Walk
SUB-TOTAL	67.0	11.4	7.4	127.5	4080.0	30.0	40.0	40.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES