SUMMARY OF QUANTITIES

NO.	CODE NO.	ITEM	UNIT	TOTAL	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
			LOCATION		URBAN 7, 10, 11, 25, 26	18	30, 34	2	4, 8, 19	3, 6, 9, 13, 14, 15, 22	5	33	24	21	1, 16, 17, 20, 29, 35, 25, 27, 28, 31	12	32	23, 27, 28, 31	3	23
			FUNDING BREAK-DOWNS		100% STATE	95% STATE 2.5% KANE COUNTY 2.5% VILLAGE OF CARPENTERS-VILLE	95% STATE 5% VILLAGE OF EAST DUNDEE	97.5% STATE 2.5% CITY OF ELGIN	96.7% STATE 3.3% CITY OF ELGIN	95% STATE 5% CITY OF ELGIN	96% STATE 4% CITY OF ELGIN	95% STATE 5% KANE COUNTY	95% STATE 5% VILLAGE OF HUNTLEY	95% STATE 5% VILLAGE OF SOUTH ELGIN	95% STATE 5% VILLAGE OF WEST DUNDEE	96.7% STATE 3.3% DUNDEE TOWNSHIP	96.7% STATE 3.3% VILLAGE OF WEST DUNDEE	95% STATE 5% VILLAGE OF WEST DUNDEE	EVP *	EVP **
			TYPE																	
1.	67100100	MOBILIZATION	L SUM	1	1															0021
2.	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
3.	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	60	15				30		15									
4.	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	34	5	1	2	1	3	7	1	1	1	1	10	1	1	4		
5.	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3						2				1						
6.	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	9					3		2				4			2		
7.	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6											6			2		
8.	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1											1			1		
9.	87900200	DRILL EXISTING HANDHOLE	EACH	4	1				2		1									
10.	88030012	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED	EACH	2	2															
11.	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	17					3	10	2				2					
12.	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	19	1				7		3				8			4		
13.	88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1											1					
14.	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1						1										
15.	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	14					1	9					4			2		
16.	88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	16	2				3	4	3				4			2		
17.	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	11					1	5					5			2		
18.	88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2							2									
19.	88030325	SIGNAL HEAD, LED, 3-FACE, 1-3 SECTION, 1-4 SECTION, 1-5 SECTION BRACKET MOUNTED	EACH	1											1					
	88030230	SIGNAL HEAD, LED, 2-5 FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1	1															
20.	88030330	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION BRACKET MOUNTED	EACH	3						1					2					
~~21.~~	~~88055350~~	~~OPTIGALLY PROGRAMMED SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED~~	~~EACH~~	~~1~~							~~1~~									
22.	88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6						6										
23.	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	41	2		2	5	2	14	2				12		2	10		
24.	88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	5						5										
25.	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	26	1		7	1	1	5	3				8			7		
26.	88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1				1												
27.	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	31					4	19	2				6			2		

* 100% OF THE COST SHALL BE PAID BY THE CITY OF ELGIN
** 100% OF THE COST SHALL BE PAID BY THE VILLAGE OF WEST DUNDEE

1. HUNTLEY ROAD AT ELM AVENUE / ENTRANCE F
2. ILL RTE 19 (E. CHICAGO AV) AT ILL RTE 25 (LIBERTY ST)
3. ILL RTE 25 (BLUFF CITY BLVD) AT ILL RTE 25 (ST. CHARLES RD)
4. ILL RTE 25 AT BRANDT DRIVE
5. ILL RTE 25 (DUNDEE AV) / LIBERTY STREET AT CONGDON AVENUE
6. ILL RTE 25 (BLUFF CITY BLVD) AT ILL RTE 25 (LIBERTY ST)
7. ILL RTE 25 (DUNDEE AV) AT ILL RTE 25 (PAGE AV)
8. ILL RTE 25 (DUNDEE AV) AT LUDA STREET
9. ILL RTE 25 (LIBERTY ST) AT VILLA STREET
10. ILL RTE 25 AT ILL RTE 68 (BARRINGTON AV)
11. ILL RTE 25 AT ILL RTE 72
12. ILL RTE 31 AT BONCOSKY ROAD
13. ILL RTE 31 (STATE ST) AT CHICAGO STREET
14. ILL RTE 31 (STATE ST) AT W. RIVER ROAD / DAVIS ROAD
15. ILL RTE 31 (STATE ST) AT HIGHLAND AVENUE
16. ILL RTE 31 AT HILLSIDE STREET / ENTRANCE D
17. ILL RTE 31 AT KANE STREET / ENTRANCE C
18. ~~ILL RTE 31 AT W. MAIN STREET (HUNTLEY RD)~~
19. ILL RTE 31 AT MIDDLE ROAD
20. ILL RTE 31 AT SPRUCE DRIVE / ALDI ENTRANCE
21. ILL RTE 31 (LA FOX ST) AT SUNDOWN ROAD / WYNDHAM LANE
22. ILL RTE 31 (STATE ST) AT TOLLGATE ROAD
23. ILL RTE 31 AT WILLOW LANE / STROM DRIVE
24. ILL RTE 47 AT DEL WEBB BOULEVARD / OAKCREEK PARKWAY
25. ILL RTE 47 AT BURLINGTON ROAD - FLASHING BEACONS
26. ILL RTE 68 (PENNY AV) AT ILL RTE 72 (MAIN ST)
27. ILL RTE 72 (MAIN ST) AT FIRST STREET
28. ILL RTE 72 (MAIN ST) AT SECOND STREET
29. ILL RTE 72 AT LOCUST DRIVE / ENTRANCE A
30. ILL RTE 72 (MAIN ST) AT RIVER STREET
31. ILL RTE 72 AT SLEEPY HOLLOW ROAD / CARRINGTON DRIVE
32. ILL RTE 72 AT TARTANS DRIVE
33. ILL RTE 72 (HIGGINS RD) AT TYRRELL ROAD
34. ILL RTE 72 (MAIN ST) AT VAN BUREN STREET
35. ILL RTE 72 AT VILLAGE QUARTER ROAD / ENTRANCE B

GHA #4085.880

FILE NAME = 4085.880-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 1 OF 2)	F.A.P. RTE. VARIES	SECTION 2011-218-I
		DRAWN - ZCW	REVISED -				COUNTY KANE
	PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -				TOTAL SHEETS 48 / SHEET NO. 4
	PLOT DATE = 12/16/2011	DATE - 12/16/2011	REVISED -		SCALE: N.A. / SHEET NO. OF SHEETS / STA. TO STA.		CONTRACT #: 60R60
							ILLINOIS FED. AID PROJECT