

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				

WEBER ROAD AT RENWICK ROAD INTERSECTION IMPROVEMENT					UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
SP	SI	CODE NO.	ITEM DESCRIPTION	STA 0003			STP 0003	STA TRAFFIC SIGNALS 0021	TRAINEES 0042	
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	129		129		
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	684		684		
		20101000	TEMPORARY FENCE		FOOT	3,296		3,296		
		20101200	TREE ROOT PRUNING		EACH	13		13		
		20200100	EARTH EXCAVATION		CU YD	22,629		22,629		
		20800150	TRENCH BACKFILL		CU YD	9,406	5,936	3,470		
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		SQ YD	28,097		28,098		
		21101615	TOPSOIL FURNISH AND PLACE, 4"		SQ YD	31,907		31,907		
		25000400	NITROGEN FERTILIZER NUTRIENT		POUND	1,188		1,188		
		25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	1,188		1,188		
		25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	1,188		1,188		
		25100630	EROSION CONTROL BLANKET		SQ YD	792		792		
		25200110	SODDING, SALT TOLERANT		SQ YD	38,345		38,345		
		25200200	SUPPLEMENTAL WATERING		UNIT	230		230		
		28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	792		792		
*		28000305	TEMPORARY DITCH CHECKS		FOOT	3,660		3,660		
		28000400	PERIMETER EROSION BARRIER		FOOT	14,729		14,729		
		28000500	INLET AND PIPE PROTECTION		EACH	133		133		
		28100107	STONE RIP RAP, CLASS A4		SQ YD	24		24		
		28200200	FILTER FABRIC		SQ YD	24		24		
		31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"		SQ YD	102		102		
		35102400	AGGREGATE BASE COURSE, TYPE B 12"		SQ YD	1,042		1,042		
*		40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	839		839		
		40600300	AGGREGATE (PRIME COAT)		TON	1		1		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SQ YD	142		142		
		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70		TON	32		32		
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50		TON	131		131		
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70		TON	56		56		
		42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)		SQ YD	37,437		37,437		
		42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)		SQ YD	32,790	32,790			
		42001300	PROTECTIVE COAT		SQ YD	9,243		9,243		
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	492		492		
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		SQ FT	1,366		1,366		
		42400800	DETECTABLE WARNINGS		SQ FT	48		48		
*		44000100	PAVEMENT REMOVAL		SQ YD	58,952	58,952			
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"		SQ YD	168		168		
		44000200	DRIVEWAY PAVEMENT REMOVAL		SQ YD	2,037		2,037		
		44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	12,230		12,230		
		44000600	SIDEWALK REMOVAL		SQ FT	1,504		1,504		
		44003100	MEDIAN REMOVAL		SQ FT	19,475		19,475		
		48203029	HOT-MIX ASPHALT SHOULDERS, 8"		SQ YD	73		73		
		50105220	PIPE CULVERT REMOVAL		FOOT	982		982		
		542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"		FOOT	46		46		
		54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"		EACH	1		1		
		54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"		EACH	2		2		
		54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"		EACH	1		1		
		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"		EACH	1		1		
		54247100	GRATING FOR CONCRETE FLARED END SECTION 15"		EACH	1		1		

* SPECIAL PROVISION, PLAN NOTE, OR
DETAIL HAS BEEN PROVIDED.
+ SPECIALITY ITEM.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEBER ROAD AND RENWICK ROAD
SUMMARY OF QUANTITIES

SCALE:
DATE APRIL, 2011

DRAWN BY CJO
CHECKED BY MFB