

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					80% FEDERAL 20% STATE			100% LOCAL
					ROADWAY 0004 RURAL	BRIDGE 0011 RURAL	TRAINEES 0042 RURAL	ROADWAY 0004 RURAL
40600300	AGGREGATE (PRIME COAT)	TON	5.6	4.9			0.7	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	26				26	
40600990	TEMPORARY RAMP	SQ YD	26				26	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,013	1,013				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	338	304			34	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	32	32				
44000100	PAVEMENT REMOVAL	SQ YD	2,525	2,525				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	297				297	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	252	252				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	341	341				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	564	564				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1			
50105220	PIPE CULVERT REMOVAL	FOOT	255	255				
50200100	STRUCTURE EXCAVATION	CU YD	218		218			
50200300	COFFERDAM EXCAVATION	CU YD	81		81			
50201101	COFFERDAM (TYPE 1)(LOCATION-1)	EACH	1		1			
50300225	CONCRETE STRUCTURES	CU YD	82.6		82.6			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	98.0		98.0			
50300260	BRIDGE DECK GROOVING	SQ YD	441		441			
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2			
50300300	PROTECTIVE COAT	SQ YD	441		441			
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2,045		2,045			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	34,600		34,600			
* 50901050	STEEL RAILING, TYPE SM	FOOT	188		188			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	980		980			
51202305	DRIVING PILES	FOOT	980		980			
51203600	TEST PILE STEEL HP12X53	EACH	3		3			
51204650	PILE SHOES	EACH	18		18			
51500100	NAME PLATES	EACH	1		1			
54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	2	2				
54215550	METAL END SECTIONS 15"	EACH	1	1				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	108	108				

FILE NAME = P:\CBBEL_MEST Projects\2005\09-0073 HoppesPHI\Civil\Ogr\Sh\A_S00_02.dgn

WBK
WILLS BURKE KELSEY ASSOCIATES LTD.
 110 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nperris	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/3/2012	CHECKED - RPD	REVISED -
	DATE - 12/19/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 80 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2442	04-08107-00-BR	KANE	80	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
CONTRACT NO. 63644				