

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					80% FEDERAL 20% STATE			100% LOCAL
					ROADWAY 0004 RURAL	BRIDGE 0011 RURAL	TRAINEES 0042 RURAL	ROADWAY 0004 RURAL
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	400	400			
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	24		24		
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2			
	60107600	PIPE UNDERDRAINS 4"	FOOT	903	903			
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	3	3			
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
	60500060	REMOVING INLETS	EACH	1	1			
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	287.5	287.5			
*	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4			
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2			
*	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1			
	63200310	GUARDRAIL REMOVAL	FOOT	182	182			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
	67100100	MOBILIZATION	L SUM	1	1			
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4			
*	72000100	SIGN PANEL - TYPE 1	SQ FT	16	16			
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	4			
*	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6			
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4,502	4,502			
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	24	24			
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11			
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
*	A2002924	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3			
*	A2008466	TREE, ULMUS AMERICANA (AMERICAN ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	1	1			
*	B2001168	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	1	1			
*	K0013030	PERENNIAL PLANTS, WETLAND TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	4	4			
*	K1003660	MOWING CYCLES	EACH	3	3			
*	Xx008645	TEMPORARY INFORMATIONAL SIGNS	EACH	2	2			
	X0323586	PIPE DRAIN REMOVAL	FOOT	10	10			
	X0326806	WASHOUT BASIN	L SUM	1	1			
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	1.6				1.6
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	40		40		

FILE NAME = P:\CBBEL\MEST Projects\06-0073 Hoppers\PHI\Civil\Dgn\Shk\S00\_03.dgn

**WBK**  
**WILLS BURKE KELSEY ASSOCIATES LTD.**  
 116 West Main Street, Suite 201  
 St. Charles, Illinois 60174

USER NAME = nparris	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/3/2012	CHECKED - RPD	REVISED -
	DATE - 12/19/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 5 OF 80 SHEETS	STA.	TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2442	04-08107-00-BR	KANE	80	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 63644				