

SCHEDULE OF QUANTITIES

550A0090 STORM SEWERS, CLASS A, TYPE 1 18"

FOOT	LOCATION	O/S	REMARKS
66	90+55.50	91+20.70	RT
110	91+20.70	92+31.00	RT
224	92+72.60	94+97.00	RT
400	TOTAL		

60100060 CONCRETE HEADWALLS FOR PIPE DRAINS

EACH	LOCATION	O/S	REMARKS
1	90+89.70	32.8	LT
	92+15.60	28.0	LT
	92+15.60	28.0	RT
	92+88.60	28.0	LT
	92+88.60	28.0	RT
1	95+00.00	27.7	LT
2	TOTAL		

60107600 PIPE UNDERDRAINS 4"

FOOT	LOCATION	O/S	REMARKS
177	89+18.80	90+87.60	LT
127	89+50.00	90+69.70	LT
23	90+69.70	90+76.50	RT
54	94+96.88	95+00.00	LT/RT
261	95+00.00	97+60.20	LT
261	95+00.00	97+60.20	RT
903	TOTAL		

60200805 CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE

EACH	LOCATION	O/S	REMARKS
1	90+58.50	31.0	RT
1	TOTAL		

60207605 CATCH BASINS, TYPE C, TYPE 8 GRATE

EACH	LOCATION	O/S	REMARKS
1	94+96.90	31.0	RT
1	94+97.00	40.1	RT
1	95+76.30	28.0	RT
3	TOTAL		

60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID

EACH	LOCATION	O/S	REMARKS
1	91+20.70	25.0	RT
1	92+09.60	65.0	LT
1	94+96.90	25.0	RT
3	TOTAL		

60500060 REMOVING INLETS

EACH	LOCATION	O/S	REMARKS
1	RT. STA. & OFFSET	94+96.90	30.5
1	TOTAL		

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	O/S	REMARKS
25	LT. STA.	92+06.00	TO 92+31.00 ROADWAY
20	RT. STA.	92+10.00	TO 92+30.00 ROADWAY
43	LT. STA.	92+31.00	TO 92+74.00 BRIDGE
44	RT. STA.	92+30.00	TO 92+74.00 BRIDGE
25	LT. STA.	92+74.00	TO 92+99.00 ROADWAY
25	RT. STA.	92+74.00	TO 92+99.00 ROADWAY
182	TOTAL		

72000100 SIGN PANEL - TYPE 1

SQ FT	LOCATION	O/S	SQ IN	REMARKS
6.25	88+80.70	30.2	LT	900.0 R1-1
1.07	89+17.10	22.2	LT	154.0 SECFPD SIGN
6.25	91+06.10	35.6	RT	900.0 R1-1
1.07	94+43.30	17.8	LT	154.0 SECFPD SIGN
1.07	95+81.90	16.8	LT	154.0 SECFPD SIGN
16	TOTAL			

72400100 REMOVE SIGN PANEL ASSEMBLY - TYPE A

EACH	LOCATION	REMARKS
1	STA. 89+17, 22.2' RT	SECFPD SIGN
1	STA. 91+06, 36.6' RT	STOP SIGN
1	STA. 94+43, 17.8' RT	SECFPD SIGN
1	STA. 95+82, 16.8' RT	SECFPD SIGN
4	TOTAL	

FILE NAME = P:\CBBEL\WEST\Projects\2209\05-0073_Hesperia\11\Drawings\11\SCH\11\SCH011.dwg