

# PAVEMENT REMOVAL SCHEDULE

LOCATION	40600982	40600990	44000100	44000157	44000200
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	DRIVEWAY PAVEMENT REMOVAL
	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
<b>MAINLINE</b>					
87+00.00 - 87+95.00	25.7	25.7		296.6	
87+95.00 - 88+00.00			12.9		
88+00.00 - 88+20.00			51.7		
88+20.00 - 88+50.00			77.5		
88+50.00 - 89+00.00			129.1		
89+00.00 - 89+50.00			129.2		
89+50.00 - 90+00.00			128.4		
90+00.00 - 90+50.00			128.5		
90+50.00 - 91+00.00			263.6		
91+00.00 - 91+50.00			163.7		
91+50.00 - 91+89.60			100.2		
91+89.60 - 92+00.00			26.2		
92+00.00 - 92+19.10			48.0		
<b>BRIDGE</b>			57.0		
92+85.10 - 93+00.00			37.4		
93+00.00 - 93+14.60			36.7		
93+14.60 - 93+50.00			89.7		
93+50.00 - 94+00.00			126.8		
94+00.00 - 94+50.00			127.6		
94+50.00 - 95+00.00			127.0		
95+00.00 - 95+50.00			126.5		
95+50.00 - 96+00.00			127.1		
96+00.00 - 96+50.00			127.8		
96+50.00 - 97+00.00			127.9		
97+00.00 - 97+35.00			89.6		
97+35.00 - 97+50.00			38.4		
97+50.00 - 97+60.00			25.6		
<b>ENTRANCE</b>					
88+95.70					54.9
89+36.10					64.0
94+23.70					71.9
95+59.20					60.6
<b>TOTAL</b>	25.7	25.7	2,524.1	296.6	251.5
<b>ADJUSTED TOTAL</b>	26.0	26.0	2,525.0	297.0	252.0

# EROSION CONTROL SCHEDULE

LOCATION	25100630	25100635	28000250	28000305	28000400	28000500	28000510	28100107	28200200
	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	STONE RIPRAP, CLASS A4	FILTER FABRIC
	(SQ YD)	(SQ YD)	(POUND)	(FOOT)	(FOOT)	(EACH)	(EACH)	(SQ YD)	(SQ YD)
<b>MAINLINE</b>									
87+00.00 - 87+95.00	205.2		8.6		184.0				
87+95.00 - 88+00.00	19.9		0.8	10.0	10.0				
88+00.00 - 88+20.00	79.5		3.2		40.0				
88+20.00 - 88+50.00	112.7		4.7	20.0	60.0				
88+50.00 - 89+00.00	151.3		6.3	10.0	83.0				
89+00.00 - 89+50.00	132.0		5.5	20.0	80.0				
89+50.00 - 90+00.00	188.1		7.8	10.0	100.0				
90+00.00 - 90+50.00	225.5		9.3	10.0	103.0				
90+50.00 - 91+00.00	271.5		11.2	10.0	97.0	1.0	1.0		
91+00.00 - 91+50.00	371.2	6.5	12.5		88.0				
91+50.00 - 91+89.60	227.7	63.2	6.0	10.0	80.0				
91+89.60 - 92+00.00	59.8	17.0	1.3		21.0				
92+00.00 - 92+19.10	189.5	32.3	2.4	10.0	39.0				
<b>BRIDGE</b>								454.0	454.0
92+85.10 - 93+00.00	33.5	25.3	4.3	10.0	35.0				
93+00.00 - 93+14.60	32.3	23.9	2.3		30.0				
93+14.60 - 93+50.00	84.6	58.1	5.9	10.0	72.0				
93+50.00 - 94+00.00	165.3	77.1	10.0	10.0	101.0				
94+00.00 - 94+50.00	209.9	10.6	9.1		88.0		1.0		
94+50.00 - 95+00.00	301.9		12.5	10.0	56.0	1.0			
95+00.00 - 95+50.00	296.5		12.3		88.0	1.0			
95+50.00 - 96+00.00	166.5		6.9		85.0	1.0	1.0		
96+00.00 - 96+50.00	225.4		9.2		100.0				
96+50.00 - 97+00.00	232.5		9.6	10.0	109.0				
97+00.00 - 97+35.00	132.2		5.5	10.0	70.0				
97+35.00 - 97+50.00	58.3		2.4	10.0	30.0				
97+50.00 - 97+60.00	41.3		1.4	10.0	57.0				
<b>MAINTENANCE</b>	100.0	100.0		95.0	50.0		1.0		
<b>TOTAL</b>	4,314.1	414.1	170.9	285.0	2,041.0	4.0	4.0	454.0	454.0
<b>ADJUSTED TOTAL</b>	4,315.0	415.0	171.0	285.0	2,041.0	4.0	4.0	454.0	454.0

FILE NAME = P:\SUBBEL WEST Projects\28000510\28000510.dgn



USER NAME = nparriss	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - RPD	REVISED -
PLOT DATE = 12/16/2011	CHECKED - RPD	REVISED -
	DATE - 12/19/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. 11 OF 80 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2442	04-08107-00-BR	KANE	80	11
CONTRACT NO. 63644				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				