PAVEMENT SCHEDULE

LOCATION			OFF.	31101100 SUBBASE GRANULAR MATERIAL, TYPE B (SQ YD)	35501308 HOT-MIX ASPHALT BASE COURSE, 6" (SQ YD)	35501316 HOT-MIX ASPHALT BASE COURSE, 8" (SQ YD)	40300200 BITUMINOUS MATERIALS (PRIME COAT) (TON)	40600300 AGGREGATE (PRIME COAT) (TON)	40603080 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TON)	40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (TON)	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	48101500 AGGREGATE SHOULDERS, TYPE B 6" (SQ YD)	48203029 HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)	X2020110 GRADING AND SHAPING SHOULDERS (UNIT)	X4811700 AGGREGATE SHOULDER, SPECIAL (CU YD)	Z0001050 AGGREGATE SUBGRADE 12" (SQ YD)
MAINLINE																
87+00.00	-	87+95.00					0.18	0.70		33.7				1.6		
87+95.00	-	88+00.00					0.02	0.03	5.6	1.5		3.4				15.28
88+00.00	-	88+20.00					0.08	0.11	22.4	6.0		16.0				55.56
88+20.00	-	88+50.00					0.11	0.16	33.6	9.0		26.7				83.34
88+50.00	-	89+00.00					0.19	0.27	56.0	14.9		31.4				138.88
89+00.00	-	89+50.00					0.21	0.27	56.0	14.9		20.6				138.88
89+50.00	-	90+00.00					0.27	0.27	56.0	14.9		35.0				138.88
90+00.00	-	90+50.00		0.4			0.27	0.27	56.4	15.0		36.9	10.5			150.50
90+50.00	-	91+00.00		3.4			0.43	0.54	113.0	30.2		11.8	82.3			359.24
91+00.00	-	91+50.00		3.2			0.23	0.33	70.1	18.7		6.0	77.5			250.74
91+50.00	-	91+89.60		2.5			0.15	0.21	44.4	11.4	16.0		59.2			169.19
91+89.60	-	92+00.00		0.2									5.2			61.53
92+00.00	-	92+19.10		0.4									9.6		4.0	79.58
BRIDGE																
92+85.10	-	93+00.00		0.3									7.4		4.0	62.08
93+00.00	-	93+14.60		0.3									7.3			60.84
93+14.60	-	93+50.00		2.1			0.18	0.19	39.6	10.6	16.0		49.1			147.50
93+50.00	-	94+00.00		3.1			0.27	0.27	56.0	14.9			74.2			213.15
94+00.00	-	94+50.00		1.7			0.23	0.27	56.0	14.9			40.3			180.26
94+50.00	-	95+00.00		1.5			0.23	0.27	56.0	14.9		18.0	34.7			180.10
95+00.00	-	95+50.00		1.5			0.23	0.27	56.0	14.9		17.5	34.7			173.61
95+50.00	-	96+00.00		1.8			0.24	0.27	56.0	14.9		2.1	42.0			180.82
96+00.00	-	96+50.00		1.2			0.22	0.27	56.0	14.9		24.4	28.1			167.03
96+50.00	-	97+00.00		0.1			0.20	0.27	56.0	14.9		43.2	1.3			140.15
97+00.00	-	97+35.00					0.13	0.19	39.2	10.5		31.1				97.22
97+35.00	-	97+50.00					0.06	0.08	16.8	4.5		11.4				41.44
97+50.00	-	97+60.00					0.04	0.05	11.3	3.0		5.4				28.22
ENTRANCE																
88+95.70			LT	9.5		81.0				9.1						
89+36.10			RT	7.2	60.2					6.8						
94+23.70			RT	10.5	87.2					9.8						
95+59.20			RT	9.2	77.0					8.6						
NOMINAL																
TOTAL				59.9	224.4	81.0	4.17	5.52	1012.4	337.5	32.0	340.8	563.3	1.6	8.0	3314.02
ADJUSTED TOTAL				**60.0**	**225.0**	**82.0**	**4.3**	**5.6**	**1,013.0**	**338.0**	**32.0**	**341.0**	**564.0**	**1.6**	**8.0**	**3,315.0**

FILE NAME = P:\CBBEL WEST Projects\2009\09-0073 HoppePrtl\Civil\Dgn\Shts\SCHEDULE6.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
116 West Main Street, Suite 201
St. Charles, Illinois 60174

USER NAME = nparris	DESIGNED - KMA	REVISED -	
	DRAWN - RPD	REVISED -	
PLOT SCALE =	CHECKED - RPD	REVISED -	
PLOT DATE = 12/16/2011	DATE - 12/19/11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. 12 OF 80 SHEETS | STA. | TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2442	04-08107-00-BR	KANE	80	12
		CONTRACT NO.63644		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		