## SUMMARY OF QUANTITIES

| PAY ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE 0005 QUANTITY |
|---|---|---|---|---|
| 20200100 | EARTH EXCAVATION | CU YD | 44 | 44 |
| * 21400100 | GRADING AND SHAPING DITCHES | FOOT | 146 | 146 |
| 35101600 | AGGREGATE BASE COURSE, TYPE B 4" | SQ YD | 232 | 232 |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 7.3 | 7.3 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 32 | 32 |
| 40600400 | MIXTURE FOR JOINTS, CRACKS, AND FLANGEWAYS | TON | 3 | 3 |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 641 | 641 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 926 | 926 |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 246 | 246 |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50 | TON | 1,417 | 1,417 |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 230 | 230 |
| 44000161 | HOT-MIX ASPHALT SURFACE REMOVAL, 3" | SQ YD | 1,462 | 1,462 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 2,382 | 2,382 |
| 44201723 | CLASS D PATCHES, TYPE IV, 6 INCH | SQ YD | 762 | 762 |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 995 | 995 |
| 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | SQ YD | 116 | 116 |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 140 | 140 |
| 542D0217 | PIPE CULVERTS, CLASS D, TYPE 1 12" | FOOT | 160 | 160 |
| 54213867 | STEEL END SECTIONS 12" | EACH | 7 | 7 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 2 | 2 |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 3 | 3 |
| 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 5 | 5 |
| 60500060 | REMOVING INLETS | EACH | 10 | 10 |
| 60609200 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 | FOOT | 622 | 622 |

## SUMMARY OF QUANTITIES

| PAY ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE 0005 QUANTITY |
|---|---|---|---|---|
| # 63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS | FOOT | 100 | 100 |
| # 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 2 | 2 |
| # 63200310 | GUARDRAIL REMOVAL | FOOT | 107 | 107 |
| # 66900200 | NON-SPECIAL WASTE DISPOSAL | CU YD | 23 | 23 |
| # 66900450 | SPECIAL WASTE PLANS AND REPORTS | LSUM | 1 | 1 |
| # 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 1 | 1 |
| 67100100 | MOBILIZATION | LSUM | 1 | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | LSUM | 1 | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | LSUM | 1 | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 1,944 | 1,944 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 216 | 216 |
| # 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 368 | 368 |
| # 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 692 | 692 |
| # 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 108 | 108 |
| # 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 2 | 2 |
| * X0327301 | RELOCATE EXISTING MAILBOX | EACH | 5 | 5 |
| * X2020110 | GRADING AND SHAPING SHOULDERS | UNIT | 31.6 | 31.6 |
| * X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 25 | 25 |
| * X4240430 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL | SQ FT | 2,245 | 2,245 |
| * X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 7,278 | 7,278 |
| * X6023508 | INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE | EACH | 10 | 10 |
| * X6026050 | SANITARY MANHOLES TO BE ADJUSTED | EACH | 11 | 11 |
| * XX003435 | PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT | SQ YD | 113 | 113 |
| * XX006947 | HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT | SQ YD | 272 | 272 |
| * XX007278 | PARKWAY RESTORATION | SQ YD | 1,486 | 1,486 |
| * Z0004540 | HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE | SQ YD | 1,218 | 1,218 |
| * Z0004562 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 1,310 | 1,310 |
| * Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 |

* INDICATES ITEM COVERED BY SPECIAL PROVISION
\# INDICATES SPECIALTY ITEM

COPYRIGHT © 2010, BY BAXTER & WOODMAN, INC.
LICENSED TO PRINT AT ANY SCALE IN ILLINOIS
LICENSE NO. - 184-001197 EXPIRES: 4/30/2011
560kcr 2/9/2011 10:00:54 AM
...\shtrlds\sof.cfg Default.pt
...\PLOTS\00363-SHT.tbl
U:\Crystal Lake\WAFT\00363-Forest-GBH Lopp\CADD-SURVEY\DRAWINGS\00363-GENNOTES.dgn

| BAXTER & WOODMAN Consulting Engineers | | |
|---|---|---|
| DESIGNED - CAC | REVISED - | |
| DRAWN - BCD | REVISED - | |
| CHECKED - TMS | REVISED - | |
| DATE - 10-18-11 | FILE - 100363-GENNOTES.sht | |

**CITY OF OAK FOREST, ILLINOIS**
**FAU ROUTE 1059 (FOREST AVENUE / GEORGE BRENNAN HIGHWAY)**

**SUMMARY OF QUANTITIES**

SCALE: NONE | STA. | TO STA.

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 1059 | 10-00096-00-RS | COOK | 17 | 3 |
| FED. ROAD DIST. NO. | | CONTRACT NO. 63668 | | |
| | ILLINOIS | FED. AID PROJECT | | |