





### BEAM ELEVATION



SECTION A-A




SECTION B-B

Note:  
Two hardened washers shall be required over all oversized holes for new diaphragms.

### END DIAPHRAGM "D"

(Total 16 required)



### END DIAPHRAGM "D" REMOVAL DETAIL

(Total 20 Diaphragms to be removed. Cost included with Structural Steel Removal)

### BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Structural Steel	Pound	4,760
Structural Steel Removal	Pound	5,940
Stud Shear Connectors	Each	6,516

INTERIOR GIRDER MOMENT TABLE				
	0.4 Sp. 1 or 0.6 Sp. 3	Pier 1 & 2	0.5 Sp. 2	
$I_s$ (in <sup>4</sup> )	9739	9739	9738.8	
$I_c(n)$ (in <sup>4</sup> )	23569		23569	
$I_c(3n)$ (in <sup>4</sup> )	17266	17266	17266	
$I_c(cr)$ (in <sup>4</sup> )		12382		
$S_s$ (in <sup>3</sup> )	541	541	541	
$S_c(n)$ (in <sup>3</sup> )	760		760	
$S_c(3n)$ (in <sup>3</sup> )	592	592	592	
$S_c(cr)$ (in <sup>3</sup> )		603		
$Z$ (in <sup>3</sup> )				
$\rho$ (kip')	0.877	0.877	0.877	
$M_Q$ ('kip)	236.44	384.72	183.78	
$s_Q$ (kip')	0.309	0.309	0.309	
$M_sQ$ ('kip)	83.12	137.15	63.08	
$M_L$ ('kip)	384	311.47	369.52	
$M_{IM}$ ('kip)	103.3	80.6	93.8	
$s_3 [M_L + M_{IM}]$ ('kip)	812.2	653.5	772.3	
$M_a$ ('kip)	1471.2	1527.9	1324.8	
$M_u$ ('kip)	1963		1936	
$f_s \rho$ non-comp (ksi)	5.2	8.5	4.1	
$f_s \rho$ (comp) (ksi)	1.7	2.7	1.3	
$f_s (s_3 [M_L + M_{IM}])$ (ksi)	1.1	1.1	1.0	
$f_s$ (Overload) (ksi)	19.8	24.3	17.5	
$f_s$ (Total) (ksi)		31.5		
VR (k)	53.89	57	42.66	

INTERIOR GIRDER REACTION TABLE		
	W. Abut. & E. Abut.	Pier 1 & 2
$R_Q$ (k)	56.1	87.4
$R_L$ (k)	38.13	41.69
$R_I$ (k)	10.25	11.2
$R_{Total}$ (k)	104.48	140.29

\* Compact section

\*\* Braced non-compact and partially braced section.

\*\*\* Includes Approach Slab Dead Load Reaction at abutments.

USER NAME = dheberling	DESIGNED -	BRD	REVISED -	WHKS & co.
FILE NAME = 0430004&5-64C94.dwg	CHECKED -	SDS	REVISED -	7018 KINGSMILL CT., SPRINGFIELD, IL (217) 483-9457
PLOT DATE = 12/6/2011	DRAWN -	DLH	REVISED -	DESIGN FIRM #184001036
PLOT TIME = 10:07:27 AM	CHECKED -	BRD/SDS	REVISED -	ENGINEERING

7018 KINGSMILL CT.,  
SPRINGFIELD, IL  
(217) 483-9457  
DESIGN FIRM #184001036

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS  
STRUCTURE NO. 043-0004 & 043-0005

SHEET NO. 19 OF 27 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	HEET NO.
301	(43B, 44B, 44HB, 45BD)	JO DAVIESS	309	132
				CONTRACT NO. 64C94
				ILLINOIS FED. AID PROJECT