

		20200100				25000310	28000250
	LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (CU YD)	SEEDING CLASS 4 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (POUND)
Drainage Ditch							
	10+40 TO 16+00	1170.1	877.6	148.7	728.9	0.42	42.1
	16+00 TO 21+20	512.2	384.2	4.4	379.8	0.54	54.0
	TOTALS	1682.3	1261.7	153.1	1108.6	0.96	96.1