

## <u>GENERAL NOTES</u>

Precast culvert alternate is not allowed.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. Reinforcement bars designated (E) shall be epoxy coated.

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Layout of the slope protection system may be varied in the field to suit ground conditions as directed by the Engineer.

Excavation behind existing abutment walls shall be performed to balance front and back soil pressure before removing the existing superstructure. The Contractor shall sawcut the upper portion of the existing abutment at the stage removal line before Stage I removal to ensure the remaining portion will not be prematurely damaged.

Structure excavation for the box culvert will not be measured or paid for separately, and the cost shall be included in other related items according to Article 502.13 of the Standard Specifications.

The structure excavation and backfill shall be as shown on roadway plan sheet titled "Detail of Excavation and Backfill for Box Culverts". Pay items indicated on that sheet are included in the roadway plans Summary of Quantities.

APPROVED Structural Adequacy Only T Engineer of Bridges & Structures

ŧ

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL	
Stone Riprop, Class A4	Sq Yd	198	
Filter Fabric	Sq Yd	198	
Removal Of Existing Structures No. 2	Each	1	
Concrete Superstructure	Cu Yd	5.3	
Reinforcement Bars	Pound	1400	
Reinforcement Bars, Epoxy Coated	Pound	32560	
Bar Splicers	Each	86	
Name Plates	Each	1	
Concrete Box Culverts	Cu Yd	154.1	
Hot-Mix Asphalt Surface Removal (Deck)	Sq Yd	17	
Geotextile Retaining Wall	Sq Ft	110	
Temporary Soil Retention System	Sq Ft	313	



ELEVATION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
078–2010	698	(2) BR-1 & BR-2	PUTNAM	71	40		
		STA, 203+04	CONTRACT	NO. 0	58571		
8 SHEETS	ILLINOIS FED. AID PROJECT						