

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	QUANTITY (UNIT)
F. A. P. 384 (IL 96)	
PARCEL # 6025109	
STA. 785+92.00, 107.64' LT, 14' Dia	14
STA. 786+09.00, 160.19' LT, 12' Dia	12
STA. 786+23.00, 58.27' LT, 9' Dia	9
STA. 787+75.00, 132.63' LT, 15' Dia	15
STA. 787+90.00, 73.59' LT, 6 & 7' (x2) Dia	20
STA. 787+94.00, 88.03' LT, 14' Dia	14
STA. 788+09.00, 163.61' LT, 14' Dia	14
STA. 788+10.00, 159.24' LT, 14' Dia	14
STA. 788+16.00, 140.05' LT, 8' Dia	8
PARCEL # 6025108	
STA. 789+43.00, 53.00' LT 6, 9, 10(x2) & 13' Dia	48
PROJECT TOTAL	168

BUILDING REMOVAL NO.

LOCATION	QUANTITY (L SUM)
F. A. P. 384 (IL 96)	
PARCEL # 6025108	
*1 STA. 788+78.00, 88.76' LT	1
*2 STA. 788+98.00, 133.71' LT	1
*3 STA. 789+23.00, 133.71' LT	1
PARCEL # 6025109	
*4 STA. 786+95.00, 86.47' LT	1
*5 STA. 787+34.00, 125.43' LT	1
*6 STA. 787+34.00, 175.93' LT	1
*7 STA. 786+88.00, 160.47' LT	1
*8 STA. 785+92.00, 149.96' LT	1
*9 STA. 785+49.00, 171.10' LT	1
PROJECT TOTAL	9

TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	QUANTITY (UNIT)
F. A. P. 384 (IL 96)	
PARCEL # 6025109	
STA. 786+17.00, 137.05' LT, 16' Dia	16
STA. 786+41.00, 73.49' LT, 37' Dia	37
STA. 787+28.00, 154.16' LT, 25' Dia	25
PARCEL # 6025108	
STA. 789+04.00, 53.290' LT 32' Dia	32
STA. 789+41.00, 78.21' LT 32' Dia	32
PROJECT TOTAL	142

SEALING ABANDONED WATER WELLS

LOCATION	QUANTITY (EACH)
F. A. P. 384 (IL 96)	
PARCEL # 6025109	
STA. 786+60.00, 104.60' LT	1
PARCEL # 6025108	
STA. 789.41.00, 110.10' LT	1
PROJECT TOTAL	2

REMOVAL AND DIPOSAL OF FRIABLE ASBESTOS, BUILDING NO 1

LOCATION	QUANTITY (L SUM)
F. A. P. 384 (IL 96)	
PARCEL # 6025109	
STA. 788+78.00, 88.76' LT	1
PROJECT TOTAL	1

FILLING EXISTING SEPTIC TANK

LOCATION	QUANTITY (EACH)
F. A. P. 384 (IL 96)	
PARCEL # 6025109	
STA. 786+73.00, 106.15' LT	1
PARCEL # 6025108	
STA. 786+73.00, 106.15' LT	1
PROJECT TOTAL	2