

TRAFFIC SIGNAL GENERAL NOTES

THIS TRAFFIC SIGNAL PROJECT IS LOCATED AT THE INTERSECTIONS OF 15TH STREET & STATE STREET, 12TH STREET & STATE STREET AND 11TH STREET & STATE STREET IN THE CITY OF LAWRENCEVILLE, LAWRENCE COUNTY. THE WORK INCLUDED IN THIS SECTION CONSISTS OF THE REMOVAL AND REPLACEMENT OF TRAFFIC SIGNAL HEADS, PEDESTRIAN SIGNAL HEADS, PEDESTRIAN PUSH-BUTTONS AND INSTALLING AUDIBLE PEDESTRIAN SIGNALS AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL HARDWARE SHALL BE TIGHTENED AND WELL SECURED.

ALL THREADS OF BOLTS USED IN ASSEMBLY OF TRAFFIC SIGNAL COMPONENTS SHALL BE COATED WITH A NON-LEAD BASED ANTI-SEIZE COMPOUND, SIMILAR TO LEAD PLATE, PRIOR TO ASSEMBLY.

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 PLAN LAYOUT AND BILL OF MATERIALS-15th & STATE ST
- 5 PLAN LAYOUT AND BILL OF MATERIALS-12th & STATE ST
- 6 PLAN LAYOUT AND BILL OF MATERIALS-11th & STATE ST

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 6:

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 701006-03 OFF-ROAD OPERATIONS, 2L, 2W, 12' TO 24" FROM PAVEMENT EDGE
- 701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701901-02 TRAFFIC CONTROL DEVICES
- 880006-01 TRAFFIC SIGNAL MOUNTING DETAILS

FILE NAME =	USER NAME = administrator	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS GENERAL NOTES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
al:\pwork\pvidot\steffenk\d0272652\074538-shi-index.dgn	PLOT SCALE = 20.0000' / in.	DRAWN -	REVISED -			1807	*	Lawrence	6	2	
	PLOT DATE = 12/9/2011	CHECKED -	REVISED -			CONTRACT NO. 74538					
		DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.