

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				F(L24E) HSIP(LS3E)		SUMMARY OF QUANTITIES				F(L24E) HSIP(LS3E)	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				0005 80% FED 20% STATE	0021 90% FED 10% STATE					0005 80% FED 20% STATE	0021 90% FED 10% STATE
20200500	EARTH EXCAVATION (WIDENING)	CU YD	306		306	40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	4103	4103	
20400800	FURNISHED EXCAVATION	CU YD	143		143	40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1	
*25000200	SEEDING, CLASS 2	ACRE	0.7		0.7	40800030	AGGREGATE (PRIME COAT)	TON	1	1	
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63		63	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25	25	
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63		63	44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	31650	31650	
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63		63	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	17234	17234	
*25100115	MULCH, METHOD 2	ACRE	1.4		1.4	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	32854	32854	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	63		63	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1378	1378	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1735		1735
40600300	AGGREGATE (PRIME COAT)	TON	141	141		48203100	HOT-MIX ASPHALT SHOULDERS	TON	259	259	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1967	1967		64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	4618		4618
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	264	264		67100100	MOBILIZATION	L SUM	1	1	
40600990	TEMPORARY RAMP	SQ YD	81	81							

*SPECIALTY ITEM

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\conoverpj\d0212697\d8	6e52-sh-t-plen.dgn	DRAWN -	REVISED -			*	(10-1,1)RS-3	WASHINGTON	18	4
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			*322/821		CONTRACT NO. 76E52		
	PLOT DATE = 12/15/2011	DATE -	REVISED -			FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.