

FILE NAME = S:\Projects\2009_0085\09-22 ESCA P1B 151 51 Phase 1 I1 D9\Work Order 8\CA00\CA00 Sheets\N 039-2029\0978197-shit-schedule.dgn
MODEL = Default
PLOT DRIVER = V8i,PDF,11x17,pltf9

EARTHWORK SCHEDULE						
	SUITABLE EARTH EXCAVATION	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SUITABLE INCIDENTAL EXCAVATION MATERIAL	SUITABLE INCIDENTAL EXC. MATERIAL ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
LOCATION	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
NW & SW QUADRANT CUTS & FILLS	37	28			32	-4
NE & SE QUADRANT CUTS & FILLS	64	48			9	+39
EXCAVATION FOR PGE & CAPPING	380	285				+285
EXCAVATION FOR RIPRAP	125•	0				0
EXCAVATION FOR CULVERT			100	75		+75
TOTALS	606	361	100	75	41	+395

NOTES:
1. EXCAVATION USED AS EMBANKMENT = (SUITABLE EARTH EXCAVATION + SUITABLE INCIDENTAL EXCAVATION)*0.75
• NOT SUITABLE AS EMBANKMENT

EROSION CONTROL SCHEDULE			
	TEMPORARY EROSION CONTROL SEEDING (2 APPS)	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
LOCATION	POUND	FOOT	EACH
NW QUADRANT CUTS & FILLS	10	164	
NE QUADRANT CUTS & FILLS	2	143	3
SW QUADRANT CUTS & FILLS	6	212	
SE QUADRANT CUTS & FILLS	4	153	
TOTALS	22	672	3

SEEDING SCHEDULE							
	SEEDING, CLASS 2A	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURE GROUND LIMESTONE	MULCH, METHOD 2
LOCATION	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
NW QUADRANT CUTS & FILLS	0.054	0.054	5	5	5	0.11	
NE QUADRANT CUTS & FILLS	0.014	0.014	1	1	1	0.03	0.06
SW QUADRANT CUTS & FILLS	0.034	0.034	3	3	3	0.06	0.07
SE QUADRANT CUTS & FILLS	0.023	0.023	2	2	2	0.05	0.07
TOTALS	0.125	0.125	11	11	11	0.25	0.20

GUARDRAIL REMOVAL SCHEDULE	
	FOOT
LOCATION	
SN 039-2029 - (IL 3) RT	80
SN 039-2029 - (IL 3) LT	230
TOTAL	310

TREE REMOVAL SCHEDULE	
	TREE REMOVAL, ACRES
LOCATION	ACRE
STA 369+68, 43' RT TO 370+01, 48' RT	0.125
STA 370+21 TO 370+92, 40' RT	0.125
TOTAL	0.25

F & E ROW MARKERS SCHEDULE	
	F&E ROW MARKERS
LOCATION	EACH
STA 371+50.00, 40' RT	1
STA 371+50.00, 50' RT	1
STA 372+00.00, 40' LT	1
STA 372+00.00, 45' LT	1
TOTAL	4

REMOVAL SCHEDULE	
	PAVEMENT REMOVAL
LOCATION	SQ YD
STA 370+37.00 TO 371+11.00 (EX RDWY)	219
STA 370+37.00 TO 371+11.00 (STG 1 WIDEN-RT)	37
STA 369+18.06 TO 370+30.99 - RT	51
STA 369+89.78 TO 370+26.62 - LT	21
TOTAL	328

PAVEMENT MARKING SCHEDULE				
	DESCRIPTION	SHORT-TERM PAVEMENT MARKING ①	PAINT PAVEMENT MARKING - LINE 4"	TEMP PAVEMENT MARKING - LINE 4"
LOCATION		FOOT	FOOT	FOOT
STA 367+49.50 TO 374+10.50, CL	YELLOW SKIP-DASH	136	166	166
STA 369+23.30 TO 372+21.17, RT	WHITE EDGE	24•	298	298
STA 369+20.14 TO 372+38.95, LT	WHITE EDGE	32•	319	319
TOTALS		192	783	783

① INCLUDES 1 ADDITIONAL APPLICATION
• 4' WHITE STRIPES @ 45° ANGLE @ 100' CTS

WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE			
	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
LOCATION		SQ FT	SQ FT
STA 367+49.50 TO 374+10.50, CL	YELLOW SKIP-DASH	55	39
STA 369+23.30 TO 372+21.17, RT	WHITE EDGE	100	100
STA 369+20.14 TO 372+38.95, LT	WHITE EDGE	107	
STA 369+20.14 TO 370+37.00, LT	WHITE EDGE		39
STA 371+11.00 TO 372+38.95, LT	WHITE EDGE		43
TOTALS		262	221

PIPE CULVERT SCHEDULE			
	PIPE CUL, CL D, TY 1 24"	PIPE CUL REMOVAL	PRECAST REINF CONC FLARED END SEC 24"
LOCATION	FT	FT	EACH
STA 369+22.00 TO 369+69.00, 38' RT	48		2
STA 369+55.00, 35' RT		48	
TOTALS	48	48	2

BASE COURSE SCHEDULE	
	BASE COURSE WIDENING, 10"
LOCATION	SQ YD
STA 369+10.00 to 372+27.00, RT	159
STA 369+10.00 TO 372+49.00, LT	170
TOTAL	329

SHOULDER SCHEDULE		
	HMA SHOULDERS, 8"	AGG SHLD TYPE A, 6"
LOCATION	SQ YD	TON
STA 369+92.21 TO 372+22.00, RT	187	
STA 370+20.73 TO 373+09.00, LT	204	
STA 369+61.24 TO 369+96.08, RT		6
TOTAL	391	6

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE			
	RRPM	REPLACEMENT REFLECTOR	RRPM, REFLECTOR REMOVAL
LOCATION	EACH	EACH	EACH
STA 368+35.00		1	1
STA 369+15.00		1	1
STA 369+95.00		1	1
STA 370+75.00	1		
STA 371+55.00		1	1
STA 372+35.00		1	1
STA 373+15.00		1	1
STA 373+95.00		1	1
TOTALS	1	7	7

PCC PAVEMENT SCHEDULE		
	PCC PAVEMENT 10"	PAVEMENT FABRIC
LOCATION	SQ YD	SQ YD
STA 370+37.00 TO 371+11.00	214	214
TOTALS	214	214

GUARDRAIL SCHEDULE									
	SPBGR, TYPE A, 6 FOOT POSTS	SPBGR, (SHORT RADIUS)	TRAFFIC BARRIER TERMINAL			GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKER, DIRECT APPLIED	STEEL RAILING, TYPE 2399
LOCATION	FOOT	FOOT	TYPE 6A	TYPE 6A (SPECIAL)	TYPE 1 (SPECIAL) TANGENT	EACH	EACH	EACH	FOOT
STRUCTURE NO. 039-2029 - NW	37.5		1		1	3		1	
STRUCTURE NO. 039-2029 - NE		12.5		1		1			
STRUCTURE NO. 039-2029 - SW	100		1		1	3		1	
STRUCTURE NO. 039-2029 - SE		12.5		1		1			
STRUCTURE NO. 039-2029 - HEADWALLS							2		58
TOTALS	137.5	25	2	2	2	8	2	2	58

 QUIGG ENGINEERING INC	USER NAME = mmann	DESIGNED - MCV	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES STRUCTURE NO. 039-2029			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - CMM	REVISED -					312	123B-4	JACKSON	58	6
	PLOT SCALE = 40.0000 ' / in.	CHECKED - MTM	REVISED -		SCALE: N.T.S.			SHEET NO. 1 OF 1 SHEETS			CONTRACT NO. 78197	
	PLOT DATE = 12/6/2011	DATE - 11/10/11	REVISED -		STA. TO STA.			ILLINOIS FED. AID PROJECT				