·····					İ	PIPE CU	LVERTS	8
LOCATION		DESCRIPTION	542C0220 542C5479 TYPE 1 CLASS C (CMP)		54210189 PIPE ELBOW	54215769 METAL END SEC	SEE NOTES TRENCH	COMMENTS
STA	SIDE		15"	24" EQRS	24" EQRS	24" EQRS	BACKFILL	
<del></del>			FOOT	FOOT	EACH	EACH	CUYD	
8+69	LT/RT	CULVERT EXT	17				1	
23+04	LT	CULVERT EXT		12	1	1	2	CONNECT TO EXIST 24" CMP ARCH CULVERT (INCLUDED IN PIPE COST)
	-							
TOTALS	TOTALS		17	12	1	1	3	

NOTES

1. LENGTHS DO NOT INCLUDE END SECTIONS OR ELBOWS WHICH ARE PAID FOR SEPARATELY.

2. TRENCH BACKFILL WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE CULVERTS AND FITTINGS.

		UTILIT	Y ADJUS	STMENTS	
		ADJUST	MENTS	***************************************	
		56400300	60266600		
LOCA	ATION	FIRE	VALVE	COMMENTS	
STA	SIDE	HYDRANTS	BOXES		
		EACH	EACH		
14+06	LT		3		
23+06	LT / RT	1	2		
	<u> </u>		<del></del>		
TOTALS		1	5		

				FEN	CES	
	LOC	ATION	SIDE	X6640560 CHAIN LINK FENCE, 6' (SPECIAL)	Z0055800 RUSTIC RAIL FENCE	COMMENTS
			T	FT	FT	
8+53	TO	8+77	RT		24	
17+15	TO	18+09	LT	94		
19+12	TO	20+40	LT	128		
TOTALS				222	24	

FILE NAME =	USER NAME = PAR	DESIGNED - BAJ	REVISED -		1ST STREET SIDEWALK	F.A. SECTION COUNTY TOTAL SHEET
SHT-SCHEDULE.DGN		DRAWN - PAR	REVISED -	STATE OF ILLINOIS		10-00019-00-SW ROCK ISLAND 40 9
	PLOT SCALE = 1*=1'	CHECKED - BAJ	REVISED -	DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	CONTRACT NO. 85555
	PLOT DATE = Ø1-13-12	DATE ~ 01-13-12	REVISED -		SCALE: SHEET NO. 2 OF 2 SHEETS STA. 7+63,74 TO STA. 23+59,93	ILLINOIS FED. AID PROJECT