

SUMMARY OF QUANTITIES

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	CONSTRUCTION CODE 0011 TOTAL QUANTITY	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	CONSTRUCTION CODE 0011 TOTAL QUANTITY
	20100500	TREE REMOVAL, ACRES	ACRE	0.2		50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1
	20200100	EARTH EXCAVATION	CU YD	403		50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1
	20200200	ROCK EXCAVATION	CU YD	9		50300225	CONCRETE STRUCTURES	CU YD	349.1
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	64		50300255	CONCRETE SUPERSTRUCTURE	CU YD	217
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1313		50300260	BRIDGE DECK GROOVING	SQ YD	307
BDE	25000210	SEEDING, CLASS 2A	ACRE	0.3		50300280	CONCRETE ENCASEMENT	CU YD	25.0
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27		50300300	PROTECTIVE COAT	SQ YD	658
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	GBSP	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27		50500505	STUD SHEAR CONNECTORS	EACH	1062
BDE	25100630	EROSION CONTROL BLANKET	SQ YD	939		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70880
BDE	25100115	MULCH, METHOD 2	ACRE	0.6		50800515	BAR SPLICERS	EACH	65
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120		51100300	SLOPE WALL 6 INCH	SQ YD	120
	28000400	PERIMETER EROSION BARRIER	FOOT	1302		51201600	FURNISHING STEEL PILES HP12X53	FOOT	102
	28000500	INLET AND PIPE PROTECTION	EACH	1		51201900	FURNISHING STEEL PILES HP14X89	FOOT	536
	28100209	STONE RIPRAP, CLASS A5	TON	90		51500100	NAME PLATES	EACH	2
	28200200	FILTER FABRIC	SQ YD	60		51604000	DRILLED SHAFT IN ROCK	CU YD	3
	35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	132		52000110	PREFORMED JOINT STRIP SEAL	FOOT	33
	40200500	AGGREGATE SURFACE COURSE, TYPE B, 6"	SQ YD	17		52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6
SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	205		52100520	ANCHOR BOLTS, 1"	EACH	24
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	679		54002110	EXPANSION BOLTS 7/8 INCH	EACH	45
BDE	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	14		542A1933	PIPE CULVERTS, CLASS A, TYPE 3 48"	FOOT	100
BDE	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	711		58700300	CONCRETE SEALER	SQ FT	165
BDE	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	261	GBSP	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	162
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15		60255500	MANHOLES TO BE ADJUSTED	EACH	2
	42001300	PROTECTIVE COAT	SQ YD	242		60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	FOOT	298
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35		60605000	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24	FOOT	661
	44000100	PAVEMENT REMOVAL	SQ YD	1452		61100605	MISCELLANEOUS CONCRETE	CU YD	1
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	125	SI, BDE	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	104	SI	63100167	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	EACH	2
	44000600	SIDEWALK REMOVAL	SQ FT	98	SI	63200310	GUARDRAIL REMOVAL	FOOT	457
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	162		66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4
GBSP	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		66700205	PERMANENT SURVEY MARKERS TYPE I	EACH	4
	50102400	CONCRETE REMOVAL	CU YD	11.0		67100100	MOBILIZATION	L SUM	1
GBSP	50200100	STRUCTURE EXCAVATION	CU YD	90		72000100	SIGN PANEL - TYPE 1	SQ FT	6.3
	50200300	COFFERDAM EXCAVATION	CU YD	715		72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	13

SP=SPECIAL PROVISION SI=SPECIALITY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT GBSP=GUIDE BRIDGE SPECIAL PROVISION RSP = RECURRING SPECIAL PROVISION

FILE NAME = vt\2987\2987q001.dgn

USER NAME = shughes	DESIGNED -	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	DRAWN -	REVISED -
PLOT DATE = 12/22/2011	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.U. 3799 (RIVER RD.) SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE. 3799	SECTION 08-00036-00-BR	COUNTY KENDALL	TOTAL SHEETS 54	SHEET NO. 3
CONTRACT NO. 87509			ILLINOIS FED. AID PROJECT	