

GENERAL NOTES:

- ALL WORK TO BE COMPLETED BY ELECTRICAL CONTRACTOR UNLESS NOTED OTHERWISE.
- 2. REFER TO CIVIL DRAWINGS FOR LIMITS OF EXISTING CONCRETE SIDEWALK REMOVAL (BY GENERAL CONTRACTOR).
- 5. EXISTING STREET LIGHTING SHALL REMAIN FUNCTIONAL DURING INSTALLATION OF NEW LIGHT POLES. COORDINATE REMOVAL OF EXISTING STREET LIGHTS, POLES AND FOUNDATIONS WITH AMEREN UPON COMPLETION OF WORK. EXISTING STREET LIGHTS AND POLES ARE OWNED AND TO BE REMOVED BY AMEREN.
- 4. EXITING UNDERGROUND UTILITIES ARE PLOTTED FROM AVAILABLE INFORMATION AND ARE ONLY APPROXIMATE. ADDITIONAL UTILITIES MAY BE ENCOUNTERED DURING EXACATION. EXACT LOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR BEFORE CONSTRUCTION IS STARTED. CONTACT JULLIE. (1–800–892–0123) 48 HOURS PRIOR TO DIGGING.

DEMOLITION KEYED NOTES:

- ① EXISTING LIGHT FIXTURE AND POLE TO BE REMOVED BY AMEREN. FOUNDATION TO BE REMOVED BY GENERAL CONTRACTOR.
- ② EXISTING 240V STREET LIGHT CONDUCTORS TO BE REMOVED BY AMEREN.
- 3 EXISTING 120V RECEPTACLE CONDUCTORS TO BE REMOVED.
- 4 EXISTING OVERHEAD PRIMARY CONDUCTORS TO REMAIN.
- (5) EXISTING UTILITY POLE TO REMAIN
- 6 EXISTING MILBANK ELECTRICAL CONTROL BOX TO REMAIN.
- TEXT EXECUTION EXECUTION EXECUTION OF THE PROPERTY OF THE PROP
- 8 EXISTING OVERHEAD CABLE/TELEPHONE CONDUCTORS TO BE REMOVED BY UTILITY OWNER.
- (9) EXISTING OVERHEAD SECONDARY/SERVICE DROP TO REMAIN.
- (O) EXISTING METER CABINET TO REMAIN. REMOVE OVERHEAD WEATHERHEAD AND CONDUIT. PROVIDE CLOSURE FITTING ON TOP OF METER CABINET.
- ① EXISTING OVERHEAD SERVICE CONDUCTORS TO BE REMOVED BY ELECTRICAL CONTRACTOR.

McDonough-Whitlow, P.C.

Consulting Engineers & Land Surveyors

138 East Wood Street Phone: 217,332,9333 Fax: 217,532,6500

DRAWING DATE 10/14/11 DESIGNED BY MJF DRAWN BY GDG CHECKED BY GWW

BY DATE REVISION STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DETAILS

ENLARGED ELECTRICAL DEMOLITION

ROJECT NO.	11-095	F.A.U. RTE.		SECTION			COUNTY	TOTAL SHEETS	SHEET NO.
	~		10	-00035	5-00-LS	S	Montgomery	92	79
ENAME	E1.6.dwg						CONTRACT NO.	93	563
RAWING SCALE	1"=20'	FED.	ROAD DIST.	NO	ILLINOIS	FED. A	AID PROJECT		