



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 20, 2018

SUBJECT: FAS 190 (Emerson Road)
Section 16-00225-00-RS
Whiteside County
Contract No. 85667
Item 109
March 9, 2018 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page 1 of the Schedule of Prices.**
- 2. Revised Plan Sheets 4 – 6.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Jack A. Elston, P.E.
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.
Engineer of Project Management

SUMMARY OF QUANTITIES

FAS Rte 190 & FAU Rte 5568
(C.H. 41 Emerson Rd)
Sec. 16-00225-00-RS
Whiteside County

Construction Type Codes
0005 Local Funds

ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	EMERSON ROAD	EMERSON ROAD DRAINAGE
21400100	GRADING AND SHAPING DITCHES	FOOT	150		150
28100103	STONE RIPRAP, CLASS A2	SQ YD	67.8		67.8
30201700	PORTLAND CEMENT	TON	130.1	130.1	△
35101400	AGGREGATE BASE COURSE, TYPE B	TON	300.4	300.4	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	1042.3	1042.3	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	10,186	10,186	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	35,610	35,610	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3207.3	3207.3	
40600990	TEMPORARY RAMP	SQ YD	677	677	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N50	TON	9792.1	9792.1	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	12,461	12,461	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1226.5	1226.5	
54213453	END SECTIONS, 18"	EACH	4		4
54213471	END SECTIONS 36"	EACH	2		2
54213495	END SECTIONS, 60"	EACH	4		4
54214317	END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	2		2
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	32		32
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	80		80
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	46		46
542D0265	PIPE CULVERTS, CLASS D, TYPE 1 60"	FOOT	84		84
542D5497	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	44		44
67100100	MOBILIZATION	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2384	2384	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	691	691	
△ 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	109.2	109.2	
△ 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	80,521	80,521	
△ 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1535	1535	
△ 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	718	718	
△ 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	61	61	
△ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	142	142	△
* LR400010	CIR-FDR FOAMED ASPHALT	TON	364.3	364.3	△
* LR400740	COLD IN-PLACE RECYCLING, 4.0"	SQ YD	61,730	61,730	
* LR403300	SURFACE PROFILE MILLING	SQ YD	61,730	61,730	
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1		0.1
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	

* SPECIAL PROVISION

△ SPECIALTY ITEMS

△ Revised
2/2018

FAS Rte 190 & FAU Rte 5568
 (C.H. 41 Emerson Rd)
 Sec. 16-00225-00-RS
 Whiteside County

SCHEDULE OF QUANTITIES

Station	Length Foot	Width Foot	HMA Thick Inches	Grade & Shape Ditch Foot	Portland Cement Ton	Agg Bse Cse T-B Ton	HMA Bse Cse 10" SY	Bit Matis Prime Pound	Bit Matis Track Pound	HMA Surf Rem Bt.Jt Sq Yd	Temp Ramp Sq Yd	HMA Surf Cse Mix D N50 Ton	HMA Surf Rem 2" Sq Yd	Agg Wedge Shldr T-B Ton	Short Term Pvt Mk Foot
Emerson Road															
Sta 1+25 - 224+02	22.277	26	1.75		130.1	14.2	49.8	4970	28,360	441.4	141	7376		1226.5	2073
Sta 224+02 - 235+63	1161	26 & Var	2						3075			766	6834		247
Culvert Replacements															
						50.4	164.7								
Agnew Road (S)	17	30	Var						47	103.9		17.5			
Agnew Road (N)	17	23	Var	150					40	87.8		14.8			
(7) Misc Sideroads	17	Var	Var						324	718.2		120.8			
Mill Road	86	48	1.75			217.7	764.4	1720	344			118			
PE's & CE's	17	Var	Var						888	1856		583			
FE's & MB's	3	Var	Var					3496				156			
Galt Road	491	22	2			18.1	63.4		900		17	224	2000		
Mc Cue Road	700	25	2						1285		19	320	2856		64
Il Rte 2 Turn lane	435	12.5	2						347		500	86	771		
TOTALS				150	130.1	300.4	1042.3	10,186	35,610	3207.3	677	9792.1	12,461	1226.5	2384

Contract # 85667

Revised 2/20/18

FAS Rte 190 & FAU Rte 5568
 (C.H. 41 Emerson Rd)
 Sec. 16-00225-00-RS
 Whiteside County

SCHEDULE OF QUANTITIES

Station	Length	Width	HMA Thick	Short Term Pvt Mk Rem	Mod Ureth Pavt Mk		Mod Ureth Pavt Mk		Mod Ureth Pavt Mk	Mod Ureth Pavt Mk	Mod Ureth Pavt Mk	Raised Refl Pvt Mk Rem	CIR-FDR Foamed Asphalt	Cold In-Place Recycling 4"	Surface Profile Milling	Seeding Class 2 Special
					Sq Ft	Foot	Sq Ft	Foot								
Emerson Road																
Sta 1+25 - 115+11	11.386	26	1.75	691		67,816								61,730		
Sta 224+02 - 235+63	1161	26 & Var	2		78	6607	512	375	12	85		364.3	61,730			
Culvert Replacements																0.05
Agnew Road (S)	17	30	Var													
Agnew Road (N)	17	23	Var													0.05
(7) Misc Sideroads	17	Var	Var													
Mill Road	86	48	1.75													
PE's & CE's	17	Var	Var													
FE's & MB's	3	Var	Var													
Galt Road	491	22	2			2444	332	303	37	25						
Mc Cure Road	700	25	2			2983		40	12	32						
Il Rte 2 Turn lane	435	12.5	2			671	691									
TOTALS				691	109.2	80,521	1535	718	61	142		364.3	61,730	61,730		0.1

Contract # 85667

Revised 2/20/18