



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 28, 2006

SUBJECT: FAP Route 330
Section (102 & 102X) LS
Cook County
Contract No. 62969
Item No. 123, March 10, 2006 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents.
2. Revised pages 7 & 18 – 20 of the Special Provisions.
3. Revised page 1 of the Schedule of Prices.
4. Revised sheets 2 – 4, 6 and 8 – 13 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; Estimates; Design & Environment File

TBW:TK:jc

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT 1
DESCRIPTION OF IMPROVEMENT 1
LANDSCAPE CONSTRUCTION WORK AND LANDSCAPE ESTABLISHMENT WORK..... 1
COMPLETION DATE FOR PHASE ONE 2
COMPLETION DATE FOR PHASE TWO 2
COMPLETION DATE FOR PHASE THREE..... 2
FAILURE TO COMPLETE LANDSCAPE CONSTRUCTION AND LANDSCAPE ESTABLISHMENT WORK..... 2
PLANTING WOODY PLANTS (CORRIDOR) 3
PLANTING WOODY PLANTS (TREE MITIGATION) 4
MOWING 6
RESTORATION OF DISTURBED AREAS 7
SUPPLEMENTAL WATERING 7
GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING 8
WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE 11
TRAFFIC CONTROL PLAN 12
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 12
PAYROLLS AND PAYROLL RECORDS (BDE) 13
PAYMENTS TO SUBCONTRACTORS (BDE) 14
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 15
PARTIAL PAYMENTS (BDE)..... 16
PERSONAL PROTECTIVE EQUIPMENT (BDE) 17
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 20
FLAGGER VESTS (BDE) 21

Revised 02/28/2006

RESTORATION OF DISTURBED AREAS

Description: This work shall consist of restoring grass areas within the work area. Any grass areas disturbed during construction activities shall be replaced with topsoil and seeding, Class 2A in accordance with Sections 211 and 250 of the Standard Specifications. Restoration of disturbed areas will not be paid for separately but shall be considered as included in the contract bid prices of the various types of pay items and no extra compensation will be allowed.

SUPPLEMENTAL WATERING

Scope: This work will include watering turf, trees, shrubs, vines and perennial plants at the rates specified and as directed by the Engineer.

Schedule: See the plans for supplemental watering dates. Watering will only begin after the successful completion of all period of establishment requirements.

Watering must be completed in a timely manner. When the Engineer directs the Contractor to do supplemental watering, the Contractor must begin the watering operation within 24 hours of notice. A minimum of 10 units of water per day must be applied until the work is complete. Damage to plant material that is a result of the Contractor's failure to water in a timely way must be repaired or replaced at the Contractor's expense.

Source of Water: The Contractor shall notify the Engineer of the source of water used and provide written certification that the water does not contain chemicals harmful to plant growth.

Rate of Application: The normal rates of application for watering are as follows. The Engineer will adjust these rates as needed depending upon weather conditions.

Turf and Perennial Plants: 3 gallons per square yard
Trees: 10 gallons per tree
Shrubs: 3 gallons per shrub
Vines: 2 gallons per vine

Method of Application: A spray nozzle that does not damage small plants must be used when watering perennial plants or turf. Water shall be applied at the base of the plant to keep as much water as possible off plant leaves. An open hose may be used to water trees, shrubs, and vines if mulch and soil are not displaced by watering. Water shall trickle slowly into soil and completely soak the root zone. The Contractor must supply metering equipment as needed to assure the specified application rate of water.

Method of Measurement: Supplemental watering will be measured in units of 1000 gallons (3,785 liters) of water applied as directed.

Basis of Payment: This work will be paid for at the contract unit price per unit of SUPPLEMENTAL WATERING, measured as specified. Payment will include the cost of all water, equipment and labor needed to complete the work specified herein and to the satisfaction of the Engineer.

Revised 02/28/2006

ROUTE: FAP 330 (US 12/20/45)
SECTION: (102 & 102 X) LS
COUNTY: COOK
Contract 62969

Deleted 02/28/2006

ROUTE: FAP 330 (US 12/20/45)
SECTION: (102 & 102 X) LS
COUNTY: COOK
Contract 62969

Deleted 02/28/2006

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: April 2, 2005

To account for the preparatory work and operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting in accordance with Article 108.01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

Revised 02/28/2006

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER -

62969

State Job # - C-91-227-05
PPS NBR - 1-77016-0000
County Name - COOK- -
Code - 31 - -
District - 1 - -
Section Number - (102 & 102X) LS

Project Number

Route
FAP 330

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2C026G3	T-CELTIS OCCID CG 3G	EACH	70.000				
* A2C007G3	T-AMELAN CAN CG 3G	EACH	140.000				
* A2C023G3	T-CARYA OVATA CG 3G	EACH	140.000				
* A2C033G3	T-QUERCUS COCCI CG 3G	EACH	40.000				
A2C035G3	T-JUGLANS NIGRA CG 3G	EACH	70.000				
* DELETED							
A2C049G3	T-QUERC ALBA CG 3G	EACH	180.000				
* DELETED							
A2C053G3	T-QUERCUS IMBRI CG 3G	EACH	120.000				
A2C056G3	T-QUERC MACR CG 3G	EACH	450.000				
A2C061G3	T-QUERC RUBRA CG 3G	EACH	190.000				
* DELETED							
A2002516	T-CARP CAROL 2	EACH	3.000				
* A2006600	T-QUERCUS COCCI 1-3/4	EACH	14.000				
A2006712	T-QUERCUS MACR 1-1/2	EACH	14.000				
A2007114	T-QUERCUS RUBRA 1-3/4	EACH	14.000				
* DELETED							
B2000562	T-AMELAN CAN SF 4'	EACH	50.000				
B2001164	T-CERCIS CAN CL 5'	EACH	8.000				
* REVISED : FEBRUARY 28, 2006							