

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 308 (IL 84)	109BR-3 & 109BR-4	Whiteside	47	2
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64B29				

The final top 100 mm (four inches) of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 6 (modified) shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1 (modified). Class 6 (modified) shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Meter (Cubic Yard) for FURNISHED EXCAVATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of FURNISHED EXCAVATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the FURNISHED EXCAVATION.

The following Mixture Requirements are applicable for this project:

Mixture Uses(s):	Mainline Surface Course
PG:	PG 64-22
RAP%: (Max)	10%
Design Air Voids	4.2 @ N50
Mixture Composition (Gradation Mixture)	IL 9.5 or 12.5
Friction Aggregate	C
20 Year ESAL	4.3

Install a "TO ACTUATE SIGNAL" sign for the traffic signal detector loops. The detail of this sign is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701321.

These structures will retain the same numbers 098-0022 & 098-0023.

The Contractor shall supply the Resident Engineer with the manufacturer's installation requirements for the type of Steel Plate Beam Guardrail Terminal Type 1 Special (Tangent) or Steel Plate Beam Guardrail Terminal Type I Special (Flared).

Bituminous Prime Coat shall be placed in accordance with Section 406 of the Standard Specifications. The cost of the Bituminous Prime Coat shall be included in the contract unit price per TON for BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50.

A quantity of Furnished Excavation has been included to repair washed out areas of existing slopes and to build up the shoulders throughout the job to conform with the typical sections and shoulder widening for terminals as shown in the plans. This work will be included in the contract unit price per Cubic Yard for FURNISHED EXCAVATION.

One 16d galvanized nail shall be used to toe nail the wood block out to the wood post on all Traffic Barrier Terminal Type I Specials.

Delineators shall be installed as shown in Standard 635001, except that the post shall be rotated 180° and only metal-backed delineators shall be permitted.

Delineators shall be salvaged and placed at the ends of approach guardrail terminal sections. The Contractor shall take care to not damage delineators and store in a safe manner for re-use. Damaged delineators shall be replaced at the contractor's expense.

Pavement marking shall be done according to Standard 780001, except as follows:

1. All words, such as ONLY, shall be 2.4 m (8 feet) high.
2. All non-freeway arrows shall be the large size.
3. The distance between yellow no-passing lines shall be 200 mm (8"), not 180 mm (7") as shown in the detail of Typical Lane and Edge Lines.

Permanent survey markers, Type II shall be cast-in-place as shown on Highway Standard 667101. A marker shall be placed mid point between the two structures and the other marker shall be placed at or just east of Cedar Creek in such a location that will take into account satellite and future construction. Location shall be determined by the Engineer.

The Contractor shall submit to the Engineer a description of location, elevation, and coordinates for each permanent survey marker. The Engineer shall submit this information to the Survey Crew.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Mediacom	Commonwealth Edison
Alliant Energy	Citizen's Telephone
Norlight Telecommunications	

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

IDOT
819 Depot Ave.
Dixon, IL 61021
Ph. 815/284-2271

Due to environmental concerns, the following shall be strictly adhered to:

1. All work shall be performed from the existing decks and no work shall take place below the existing structure on the ground.
2. No fill shall be placed in or around Cedar Creek or Spring Creek.

Embankment quantities for the construction of Traffic Barrier Terminals and placement of Steel Plate Beam Guardrail as shown on the plans are included in quantities for FURNISHED EXCAVATION.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.