

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308		WHITESIDE	47	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
109BR-3 & 109BR-4				

SCHEDULE OF QUANTITIES

20400800 FURNISHED EXCAVATION

CU YD	LOCATION
21	170+ 0- 173+ 0
21	219+ 40- 227+ 40
42	TOTAL

44000007 BITUMINOUS CONCRETE SURFACE REMOVA 2"

SQ YD	LOCATION
55	171+ 13- 171+ 33
56	171+ 87- 172+ 7
58	225+ 22- 225+ 42
58	225+ 89- 226+ 20
227	TOTAL

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION
54	170+ 0- 171+ 33 LT
10	172+ 83- 172+ 97 RT
10	172+ 82- 172+ 97 LT
52	170+ 0- 171+ 33 RT
34	222+ 46- 225+ 14 LT
50	219+ 46- 225+ 13 RT
28	226+ 21- 227+ 48 LT
26	226+ 14- 227+ 23 RT
264	TOTAL

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

EQ FT	LOCATION
250	222+ 58.28- 225+ 8.28 LT
550	219+ 58.23- 225+ 8.23 RT
112.5	226+ 23.36- 227+ 35.86 LT
87.5	226+ 23.21- 227+ 10.71 RT
1000	TOTAL

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION
1	171+ 0.02- 171+ 33.92 LT
1	171+ 87.24- 172+ 21.14 LT
1	171+ 87.36- 172+ 21.26 RT
1	170+ 99.86- 171+ 33.76 RT
1	225+ 8.28- 225+ 42.8 LT
1	225+ 8.23- 225+ 42.3 RT
1	226+ 23.36- 226+ 57.26 LT
1	226+ 23.21- 226+ 57.11 RT
8	TOTAL

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION
1	170+ 0.02- 170+ 12.52 LT
1	172+ 83.64- 172+ 96.14 LT
1	222+ 45.78- 222+ 58.28 LT
1	219+ 45.73- 219+ 58.23 RT
1	227+ 35.86- 227+ 48.36 LT
1	227+ 10.71- 227+ 23.2 RT
6	TOTAL

63200310 GUARDRAIL REMOVA

EQ FT	LOCATION
292	222+ 43- 225+ 35 LT
142	225+ 98- 227+ 40 LT
592	219+ 43- 225+ 35 RT
124	225+ 91- 227+ 15 RT
1150	TOTAL

63301210 REMOVE AND RE-ERECT STEEL BEAM GUARDRAIL, TYPE A

EQ FT	LOCATION
87.5	170+ 12.52- 171+ 0.02 LT
87.5	170+ 12.36- 170+ 99.86 RT
62.5	172+ 21.14- 172+ 83.64 LT
62.5	172+ 21.26- 172+ 83.66 RT
300	TOTAL

70300220 TEMPORARY PAVEMENT MARKING LINE 4"

EQ FT	LOCATION
500	169+ 0- 174+ 0L STAGE 2
500	169+ 0- 174+ 0L STAGE 2
500	169+ 0- 174+ 0R STAGE 1
500	169+ 0- 174+ 0R STAGE 1
450	223+ 50- 228+ 0L STAGE 2
450	223+ 50- 228+ 0L STAGE 2
450	223+ 50- 228+ 0R STAGE 1
3350	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVA

SQ. FT.	LOCATION
18.5	169+ 0- 174+ 0LT
1.7	169+ 0- 169+ 5LT
2.2	173+ 41- 174+ 0LT
18.5	169+ 0- 174+ 0RT
1.7	169+ 0- 169+ 46RT
0.8	173+ 78- 174+ 0RT
16.7	223+ 50- 228+ 0LT
0.6	223+ 50- 223+ 64LT
1.3	227+ 66- 228+ 0LT
62	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

EQ FT	LOCATION
542	168+ 87- 174+ 27LT
510	223+ 10- 228+ 20LT
1052	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

EQ FT	LOCATION
542	168+ 87- 174+ 27RT
510	223+ 10- 228+ 20RT
1052	TOTAL

78001110 PAINT PAVEMENT MARKING LINE 4"

EQ FT	LOCATION
1136	170+ 5- 172+ 89 WHITE EDGLINES - 2 COATS
1988	222+ 42- 227+ 39 WHITE EDGLINES - 2 COATS
142	170+ 5- 172+ 89 SKIP DASH YELLOW - 2 COATS
249	222+ 42- 227+ 39 SKIP DASH YELLOW - 2 COATS
3515	TOTAL

78100100 RAISED REFLECTIVE MARKER

EACH	LOCATION
2	171+ 13- 172+ 7
2	225+ 22- 226+ 20
4	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION
4	222+ 92- 225+ 10 LT
10	219+ 92- 225+ 10 RT
2	226+ 20- 226+ 80 LT
1	226+ 20- 226+ 64 RT
17	TOTAL

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION
1	170+ 5LT
1	170+ 6RT
1	172+ 89LT
1	172+ 89RT
1	222+ 42LT
1	227+ 39LT
6	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVA

EACH	LOCATION
2	171+ 13- 172+ 7
2	225+ 22- 226+ 20
4	TOTAL

X0323894 GUARDRAIL POST

EACH	LOCATION
1	172+ 89 RT
1	TOTAL

X0712400 TEMPORARY PAVEMENT

SQ. YD	LOCATION
130	169+ 0- 171+ 33.77 RT
121	172+ 83.43- 175+ 0 RT
186	168+ 0- 171+ 33.91 LT
38	172+ 82.37- 172+ 50 LT
118	222+ 50- 225+ 13.63 LT
44	226+ 21.12- 227+ 21.84 LT
637	TOTAL

X4066414 BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX C, N50

TON	LOCATION
7.5	171+ 13- 171+ 33
7.5	171+ 87- 172+ 7
7.5	225+ 22- 225+ 42
7.5	225+ 89- 226+ 10
30	TOTAL

X6330103 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION
1	169+ 99.86- 170+ 12.36 RT
1	172+ 83.76- 172+ 96.26 RT
2	TOTAL

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON -RE-DIRECTIVE), TEST LEVEL 3

EACH	LOCATION
1	168+ 87 LT
1	174+ 27 LT
1	223+ 10 LT
1	228+ 20 LT
4	TOTAL

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON -RE-DIRECTIVE), TEST LEVEL 3

EACH	LOCATION
1	168+ 87 RT
1	174+ 27 RT
1	223+ 10 RT
1	228+ 20 RT
4	TOTAL

PLOT DATE = Thu Dec 29 10:36:55 2005
 PLOT SCALE = 50.000000 * 7 IN.
 USER NAME = gorfj1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY