

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	G-BR-1	GRUNDY	50	9
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE - STA 554+56.21 TO 556+46.21				
LOCATION	EXCAVATION (CU YD)	ADJUSTED EX. (SHR = 0.25) FOR USE IN EMBANKMENT (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
554+80.39	2.4	1.8	0.0	1.8
555+00.00	12.6	9.4	0.6	8.8
555+41.55	11.4	8.5	0.7	7.8
555+50.00	6.1	4.6	2.6	2.0
555+75.00	8.4	6.3	15.8	-9.5
555+99.00	1.5	1.1	23.3	-22.2
556+17.94	3.9	2.9	31.0	-28.1
556+30.00	4.2	3.2	35.3	-32.1
556+50.00	3.6	2.7	36.6	-33.9
556+53.00	10.4	7.8	126.8	-119.0
558+20.00	62.1	46.6	68.7	-22.2
558+45.00	20.5	15.4	3.0	12.4
558+50.00	19.4	14.6	2.6	12.0
558+85.17	22.6	17.0	0.9	16.1
559+00.00	30.8	23.1	0.0	23.1
559+50.00	49.1	36.8	0.0	36.8
559+70.19	97.9	73.4	0.0	73.4
560+00.00	11.0	8.3	0.0	8.3
560+18.28	1.8	1.3	0.0	1.3
560+23.83	1.9	1.5	0.0	1.5
<b>TOTALS</b>	<b>382</b>	<b>286</b>	<b>348</b>	<b>-62</b>

EARTH EXCAVATION	382
FURNISHED EXCAVATION	62

1/2/2005 3:50:26 PM m:\54\oadet\valv\66563 Ecst Fork\54\oadet.dgn

default

**BOWMAN, BARRETT & ASSOCIATES INC.**  
 CONSULTING ENGINEERS  
 130 E. RANDOLPH STREET  
 CHICAGO, ILLINOIS 60601  
 JOB NO. 541



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6  
 EARTHWORK SCHEDULE

SCALE: VERT. N.T.S.  
 HORIZ. N.T.S.  
 DATE 10/25/05

DRAWN BY KAR  
 CHECKED BY DDM